

## SUMMARY OF QUANTITIES

LOCATION:

FAP 332 (IL RT 1/US 150)  
VERMILION CTY  
STA. 2912+00  
TO  
STA. 3026+00  
URBAN  
FOUR LANE  
100% STATE

LOCATION:

FAP 332 (IL RT 1/US 150)  
VERMILION CTY  
STA. 2912+00  
TO  
STA. 3026+00  
URBAN  
FOUR LANE  
100% STATE

CONSTRUCTION CODE:

1000

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,602.0
40600300	AGGREGATE (PRIME COAT)	TON	355.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	3,859.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	234.0
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	809.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	7,780.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	659.0
40800030	AGGREGATE (PRIME COAT)	TON	13.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	554
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	78,947.0
44000177	HOT-MIX ASPHALT SURFACE REMOVAL, 7"	SQ YD	2,063.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	6,587.0
44000198	HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	13,326.0
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	496.0
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	22.0
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	40.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	26.0

CONSTRUCTION CODE:

1000

60255500	MANHOLES TO BE ADJUSTED	EACH	58.0
60406500	FRAMES AND LIDS, SPECIAL	EACH	20.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2.0
67100100	MOBILIZATION	LSUM	1.0
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	LSUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17,472.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,824.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	1,436.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	51,239.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	1,291.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	316.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	874.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,095.0
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	4,567.0
Z0010900	COLD MILLING (SPECIAL)	FOOT	18,415.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	7.0

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = leroyma	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\p\1001\LEROYMA\0144976\d3505300.dgn		DRAWN -	REVISED -			332	47RS-9	VERMILION	25	5	
PLOT SCALE = 48.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 70123					
PLOT DATE = 1/29/2010		DATE -	REVISED -			FED. ROAD DIST. NO.   ILLINOIS   FED. AID PROJECT					
						SCALE: N/A	SHEET NO.	OF	SHEETS	STA. TO STA.	