

INCIDENTAL SCHEDULE									
LOCATION	AREA (As-Builts & CADD)	40800050 - Incidental HMA Surface					40600982 HMA Surf. Rem., Bt. Jt.	40800010 Bit Mtls. (Prime Coat)	40800030 Agg. (Prime Coat)
		Private Entrance	Field Entrance	Commercial Entrance	Mailbox Turnouts	Side Roads			
		SQ YD	TON	TON	TON	TON			
LT STA 70+74.14 Thornhill Dr	282.5					23.7	282.5	28.3	0.57
RT STA 70+74.14 Poland Rd	574.5					48.3	574.5	57.5	1.15
RT STA 79+30.65 Redbud Ln	158.0					13.3	158.0	15.8	0.32
RT STA 96+23.55 K's Merch.	645.0			54.2			645.0	64.5	1.29
LT STA 111+05.93 Lake Blvd	224.0					18.8	224.0	22.4	0.45
RT STA 112+58.76 Sonny Ln	303.4					25.5	303.4	30.3	0.61
LT STA 117+01.32 Dixie Acres Rd	220.9					18.6	220.9	22.1	0.44
RT STA 123+14.11 Sunset Rd	189.9					16.0	189.9	19.0	0.38
LT STA 137+05.49 Devonshire Dr	211.1					17.7	211.1	21.1	0.42
LT STA 151+46 W.Newell Rd	532.5					44.7	532.5	53.3	1.07
RT STA 166+13 Heritage Rd	232.6					19.5	232.6	23.3	0.47
LT STA 166+43.5 P.E.	25.0	2.1					25.0	2.5	0.05
RT STA 171+54.5 P.E.	73.3	6.2					73.3	7.3	0.15
RT STA 181+32 P.E.	55.0	4.6					55.0	5.5	0.11
LT STA 184+42 P.E.	37.8	3.2					37.8	3.8	0.08
RT STA 185+81 P.E.	35.0	2.9					35.0	3.5	0.07
RT STA 190+31 P.E.	107.6	9.0					107.6	10.8	0.22
RT STA 194+43 P.E.	5.8	0.5					5.8	0.6	0.01
RT STA 195+47 P.E.	35.8	3.0					35.8	3.6	0.07
RT STA 218+81 Potters Woods Rd	347.7					29.2	347.7	34.8	0.70
LT STA 218+94 Potters Woods Rd	265.4					22.3	265.4	26.5	0.53
LT STA 226+55 P.E.	26.1	2.2					26.1	2.6	0.05
LT STA 230+40 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 231+94 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 234+54 P.E.	36.7	3.1					36.7	3.7	0.07
RT STA 234+78 MBTO	10.4					0.9	10.4	1.0	0.02
LT STA 237+51 P.E.	46.1	3.9					46.1	4.6	0.09
LT STA 238+09 P.E.	23.9	2.0					23.9	2.4	0.05
RT STA 239+96 F.E.	12.7		1.1				12.7	1.3	0.03
LT STA 240+67 P.E.	41.7	3.5					41.7	4.2	0.08
RT STA 241+51 MBTO	15.2					1.3	15.2	1.5	0.03
RT STA 242+33 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 242+39 P.E.	35.6	3.0					35.6	3.6	0.07
RT STA 246+94 P.E.	44.4	3.7					44.4	4.4	0.09
RT STA 247+22 MBTO	10.4					0.9	10.4	1.0	0.02
RT STA 250+66 P.E.	44.4	3.7					44.4	4.4	0.09
RT STA 250+94 MBTO	10.4					0.9	10.4	1.0	0.02
RT STA 252+90 MBTO	11.7					1.0	11.7	1.2	0.02
RT STA 253+17 P.E.	42.2	3.5					42.2	4.2	0.08
RT STA 254+83 P.E.	34.4	2.9					34.4	3.4	0.07
RT STA 255+25 P.E.	35.6	3.0					35.6	3.6	0.07
PAGE TOTAL		71.3	2.1	54.2	4.9	297.6	5119.6	512.0	10.2

*(48-X1)RS&(48-X2,RX,RX-1)RS-1

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\bowerm\0145216\70124	Schedule.dgn	DRAWN - MLB	REVISED -					332	*	VERMILION	86	31
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = 1/26/2010	DATE - 08-20-2009	REVISED -						CONTRACT NO. 70124			