

40600990 TEMPORARY RAMP

STATION	LENGTH	WIDTH	SQ YD
LT STA 70+74.14 Thornhill Dr	7.5	30.0	25.0
RT STA 70+74.14 Poland Rd	7.5	30.0	25.0
RT STA 79+30.65 Redbud Ln	7.5	30.0	25.0
LT STA 111+05.93 Lake Blvd	7.5	30.0	25.0
RT STA 112+58.76 Sonny Ln	7.5	30.0	25.0
LT STA 117+01.32 Dixie Acres Rd	7.5	30.0	25.0
RT STA 123+14.11 Sunset Rd	7.5	30.0	25.0
LT STA 137+05.49 Devonshire Dr	7.5	30.0	25.0
LT STA 151+46 W.Newell Rd	7.5	30.0	25.0
RT STA 166+13 Heritage Rd	7.5	30.0	25.0
RT STA 218+81 Potters Woods Rd	5.0	30.0	16.7
LT STA 218+94 Potters Woods Rd	5.0	30.0	16.7
RT STA 267+61 TR 2550	5.0	30.0	16.7
LT STA 267+72 TR 2550	5.0	30.0	16.7
RT STA 320+96 TR 2650	5.0	30.0	16.7
LT STA 321+03 TR 2650	5.0	30.0	16.7
RT STA 385+48 CH 15	5.0	30.0	16.7
LT STA 385+48 CH 15	5.0	30.0	16.7
RT STA 410+94 TR 2820	5.0	30.0	16.7
LT STA 456+09 TR 2900	5.0	30.0	16.7
RT STA 475+64 TR 2940	5.0	30.0	16.7
LT STA 493+01 F.E.	5.0	30.0	16.7
LT STA 553+48 TR 3080	5.0	30.0	16.7
LT STA 615+40 TR 3200	5.0	30.0	16.7
RT STA 630+67 TR 3220	5.0	30.0	16.7
RT STA 681+28 TR 3330	5.0	30.0	16.7
LT STA 713+04 TR 3390	5.0	30.0	16.7
RT STA 747+60 TR 3450	5.0	30.0	16.7
TOTAL=			550.0
USE=			550.0

44000158 HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	
IL 1 & US 136						
62+23.58		93+00.00	3076.4	60	20509.5	
93+00.00		95+56.00	256.0	69	1962.7	
95+56.00		127+00.00	3144.0	60	20960.0	
127+00.00		130+00.00	300.0	54	1800.0	
130+00.00		136+83.00	683.0	48	3642.7	
136+83.00		138+30.00	147.0	54	882.0	
138+30.00		141+32.00	302.0	60	2013.3	
141+32.00		147+53.00	621.0	48	3312.0	
147+53.00		148+65.00	112.0	57.5	715.6	
148+65.00		150+32.00	167.0	59.5	1104.1	
150+32.00		151+46.04	114.0	48	608.2	
STA. EQ.		151+46.04	1516.8	48	8089.5	
174+83.87 BK=		166+62.82	821.0	36	3284.2	
175+02.84 AH		175+02.84	1239.7	26	3581.2	
		187+42.50	880.3	24	2347.5	
SN 092-0205		201+04.68	2477.3	24	6606.2	
		225+82.00	15147.0	22	37026.0	
		377+29.00	1719.0	22.6	4316.6	
		394+48.00	10252.0	22	25060.4	
		497+00.00	1823.0	29	5874.1	
		515+23.00	479.5	22	1172.1	
SN 092-0189		520+67.50	10032.9	22	24524.9	
SN 092-0034		624+81.00	586.0	22	1432.4	
		630+67.00	13858.0	22	33875.1	
IL 119 & US 136						
		614+26.00	626+00.00	1174.0	29	3782.9
TOTAL=					218483.2	
USE=					218484.0	

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

44000155 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"

MAINLINE SHOULDERS							
STA. EQ.	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	QUANTITY (SQ YD)
174+83.87 BK=	128+83.17		174+83.87	4600.7	16	8179.0	8179.0
175+02.84 AH	175+02.84		187+42.50	1239.7	10	1377.4	1377.4
	187+42.50		196+22.82	880.3	16	1565.0	1565.0
SN 092-0205	201+04.68		225+82.00	2477.3	16	4404.1	4404.1
	225+82.00		520+02.50	29420.5	6	19613.7	19613.7
SN 092-0189	520+67.50		621+00.40	10032.9	6	6688.6	6688.6
SN 092-0034	624+81.00		769+25.00	14444.0	6	9629.3	9629.3
IL 119 & US 136 SHOULDERS							
	614+26.00		626+00.00	1174.0	6	782.7	782.7
TOTAL=						52239.8	52239.8
USE=						52240.0	52240.0

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	AVG THICKNESS (INCHES)	AGG WEDGE TY B (TONS)		
IL 1 & US 136									
STA. EQ.		174+83.87 BK=	128+83.17	174+83.87	4600.7	6	3067.1	0.5	76.7
		175+02.84 AH	175+02.84	187+42.50	1239.7	4	551.0	0.5	13.8
			225+82.00	377+29.00	15147.0	10	16830.0	0.5	420.8
			377+29.00	394+48.00	1719.0	6	1146.0	0.5	28.7
			394+48.00	520+02.50	12554.5	10	13949.4	0.5	348.7
SN 092-0189		520+67.50	621+00.40	10032.9	10032.9	10	11147.7	0.5	278.7
SN 092-0034		624+81.00	769+25.00	14444.0	14444.0	10	16048.9	0.5	401.2
SUB-TOTAL=									1568.5
IL 119 & US 136									
		614+26.00	626+00.00	1174.0	10	1304.4	0.5		32.6
TOTAL =									1601.1
USE =									1602.0