

**78100100 - RAISED REFLECTIVE PAVEMENT MARKERS**

STATION	TO	STATION	FOOT	ONE-WAY CRYSTAL EACH	TWO-WAY AMBER EACH
62+23.58		68+90.00	666.4	17	33
68+90.00		70+20.00	130.0	7	7
71+20.00		72+50.00	130.0	7	7
72+50.00		78+90.00	640.0	16	32
79+94.00		93+54.00	1360.0	34	68
93+54.00		95+67.00	213.0	13	11
96+79.00		98+27.00	148.0	7	7
98+27.00		110+52.00	1225.0	31	61
111+56.00		112+06.00	50.0	1	3
113+15.00		116+45.00	330.0	8	17
117+52.00		122+62.00	510.0	13	26
123+70.00		125+00.00	130.0	7	7
125+00.00		129+80.00	480.0	0	24
129+80.00		147+80.00	1800.0	45	45
147+80.00		150+15.00	235.0	6	6
152+15.00		153+15.00	100.0	4	5
153+15.00		155+45.00	230.0	3	17
155+45.00		164+44.00	899.0	11	45
164+44.00		165+40.00	96.0	1	10
165+40.00		166+00.00	60.0	2	3
166+55.00		167+15.00	60.0	2	3
167+15.00		174+83.87 (BK)	768.9	0	47
175+02.84 (AH)		196+22.82	2120.0	0	26
SN 092-020	201+04.68	376+71.30	17566.6	0	220
	376+71.30	382+51.31	580.0	0	34
	382+51.31	385+31.31	280.0	7	14
	385+31.31	389+00.00	368.7	9	18
	389+00.00	394+79.41	579.4	0	34
	395+79.41	502+49.00	10669.6	0	133
	502+49.00	507+09.00	460.0	0	27
	507+09.00	508+09.00	100.0	3	5
	508+93.00	509+93.00	100.0	3	5
	509+93.00	514+53.00	460.0	0	27
	514+53.00	520+02.50	549.5	0	7
SN 092-018	520+87.50	621+00.40	10032.9	0	125
SN 092-003	624+81.00	769+25.00	14444.0	0	181
<b>US 136 / IL 119</b>					
	614+26.00	618+66.00	440.0	0	26
	618+66.00	619+66.00	100.0	3	5
	620+50.00	621+50.00	100.0	3	5
	621+50.00	626+00.00	450.0	0	26
<b>TOTAL=</b>				<b>259</b>	<b>1399</b>
<b>USE=</b>				<b>1658</b>	

**81400115 HANDHOLE TO BE ADJUSTED**

STATION		EACH
95+87	LT	1.0
96+57	LT	1.0
<b>TOTAL=</b>		<b>2.0</b>
<b>USE=</b>		<b>2.0</b>

**Z0055300 RUMBLE STRIP**

STATION		EACH
499+45	RT	1.0
505+34	RT	1.0
507+34	RT	1.0
511+69	LT	1.0
513+69	LT	1.0
519+70	LT	1.0
615+59	RT	1.0
623+26	LT	1.0
625+26	LT	1.0
<b>TOTAL=</b>		<b>9.0</b>
<b>USE=</b>		<b>9.0</b>

\*(48-X1)RS&(48-X2,RX,RX-1)RS-1

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\BOWERML\d0145216\70124	Schedules.dgn	DRAWN - MLB	REVISED -					332	*	VERMILION	86	42
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:			SHEET NO. OF SHEETS	STA.	TO STA.	CONTRACT NO. 70124	
	PLOT DATE = 1/27/2010	DATE - 08-20-2009	REVISED -		ILLINOIS FED. AID PROJECT							