CONTRACT NO. 70529

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(102X)BR,BR-3	MCLEAN	42	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF HOT-MIX ASPHALT PAVEMENT QUANTITIES

LOCATION (STA. TO STA.)	(M4400950) HOT-MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH	(M4060982) HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	(M4060100) BITUMINOUS MATERIALS (PRIME COAT)	(M4060300) AGGREGATE (PRIME COAT)	(M3110100) SUB-BASE GRANULAR MATERIAL TYPE A, 100 mm	(M3550570) HOT-MIX ASPHALT BASE COURSE, 270 mm	(M3560570) HOT-MIX ASPHALT CONCRETE BASE COURSE WIDENING, 270 mm	(M4062125) LEVELING BINDER (MACHINE METHOD) MIXTURE, N50	(M4063335) HOT-MIX ASPHALT SURFACE COURSE MIXTURE C,	(M4812000) AGGREGATE SHOULDERS, TYPE B	(M4820400) HOT-MIX ASPHALT SHOULDERS	(M4820550) HOT-MIX ASPHALT SHOULDERS 150 mm	(M4080500) INCIDENTAL HOT-MIX ASPHALT SURFACING
	SQ M	SQ M	LITER	M TON	SQ M	SQ M	SQ M	M TON	M TON	M TON	M TON	SQ M	M TON
LOCATION 1													
40+500.000 TO 40+575.000	908	--	--	--	--	--	--	--	--	--	--	--	--
40+500.000 TO 40+605.500	--	--	269.6	1.6	--	--	--	--	74.5	1.6	--	--	--
40+575.000 TO 40+595.500	248	--	--	--	--	--	--	--	--	--	--	--	--
40+605.500 TO 40+629.000	--	--	291.7	--	192.7	172	--	--	16.3	11.6	--	112.8	--
40+600.500 TO 40+632.000	--	--	--	--	--	--	--	10.8	--	--	--	--	--
40+629.000 TO 40+675.000	--	--	117.5	0.7	--	--	--	--	--	0.6	--	--	--
40+629.000 TO 40+639.000	--	--	--	--	--	--	--	--	7.7	--	--	--	--
40+639.000 TO 40+675.000	--	--	--	--	--	--	--	--	25.0	--	--	--	--
40+639.000 TO 40+675.000	435.6	--	--	--	--	--	--	--	--	--	--	--	--
40+500.000 TO 40+675.000	--	--	--	--	--	--	--	--	--	--	88.4	--	--
LOCATION 2													
43+975.000 TO 44+021.500	562.7	--	--	--	--	--	--	--	37.2	--	--	--	--
43+975.000 TO 44+033.500	--	--	149.4	0.8	--	--	--	--	--	0.8	--	--	--
44+021.500 TO 44+033.500	--	--	--	--	--	--	--	--	9.5	--	--	--	--
44+027.500 TO 44+070.000	--	--	--	--	--	--	--	19.2	--	--	--	--	--
44+031.708 TO 44+108.325	--	--	--	--	702	--	534	--	--	--	--	--	--
44+033.500 TO 44+059.000	--	--	316.5	--	209.1	186	--	--	29.3	14.2	--	--	--
44+059.000 TO 44+150.000	--	--	232.5	1.3	--	--	--	--	87.6	--	--	--	--
44+085.520 TO 44+150.000	670.7	--	--	--	--	--	--	--	--	--	--	--	--
44+108.320 TO 44+150.000	--	--	--	--	--	--	--	--	--	0.6	--	--	--
43+975.000 TO 44+150.000	--	--	--	--	--	--	--	--	--	--	59.1	--	--
INTERSECTION & CH. 21	--	360	673.0	1.5	--	--	--	--	126	32.8	--	437.2	--
DRIVEWAY LT. STA. 44+148	--	--	21.6	--	--	--	--	--	--	--	--	--	5.1
TOTAL	2,825	360	2,072	5.9	1104	358	534	30	413	62.2	164.4	550	5.1

NOTE:
INCIDENTAL ASHPALT IS A SMALL QTY.
USE MAINLINE PRIME PAY ITEMS
FOR INCIDENTAL AREA.

M2500210 SEEDING, CLASS 2A

	Ha
LOCATION 1	0.32
LOCATION 2	0.42
TOTAL	0.74

M2810201 STONE RIPRAP, CLASS A1

	CU. M
LOCATION 1	182
LOCATION 2	136
TOTAL	318

M2070220 POROUS GRANULAR EMBANKMENT

	CU. M
LOCATION 1	365
LOCATION 2	400
TOTAL	765

M2510630 EROSION CONTROL BLANKET

	SQ. M
LOCATION 1	3,210
LOCATION 2	4,170
TOTAL	7,380

LOCATION	M2830400 AGGREGATE DITCH M TON	M2820200 FILTER FABRIC FOR USE WITH RIPRAP m^2
LOCATION 1		
STA. 40+520.000 TO STA. 40+616.664 LT.	112.3	154
STA. 40+525.000 TO STA. 40+614.365 RT.	104.2	143
STA. 40+621.729 TO STA. 40+675.000 LT.	62.0	85
LOCATION 2		
STA. 43+996.556 TO STA. 44+041.386 LT.	52.5	72
STA. 44+002.222 TO STA. 44+041.380 RT.	45.9	63
STA. 44+048.621 TO STA. 44+055.929 LT.	8.7	12
STA. 44+048.614 TO STA. 44+052.969 RT.	5.0	7
STA. 44+088.407 TO STA. 44+141.109 LT.	61.2	84
STA. 44+085.969 TO STA. 44+125.077 RT.	45.2	62
TOTAL	497	682

NOTE:
LOCATION 1 IS FROM STA. 40+500 TO STA. 40+675
LOCATION 2 IS FROM STA. 43+975 TO STA. 44+150

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. ROUTE 315
SECTION (102X)BR,BR-3
MCLEAN COUNTY

DRAWN BY
DATE CHECKED BY

PLOT DATE = 1/28/2010
FILE NAME = c:\pw_work\PWIDOT\SHERERJM\d0106598\D570529-sht-schedule.dgn
PLOT SCALE = 27.0000 m / IN.
USER NAME = shererjm