

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	122 RS-4	VERMILION	42	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	FAP 840 (IL 49)	FAP 840 (IL 49)
				VERMILION CO. RURAL 100 % STATE	VERMILION CO. VIL. OF RANKIN RURAL 100% CITY
				I-000	I-000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,009.0	3,196.0	813.0
40600300	AGGREGATE( PRIME COAT)	TON	81.0	64.0	17.0
40600625	LEVEL BINDER (MACHINE METHOD), N50	TON	764.0	764.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	87.0	87.0	
40600990	TEMPORARY RAMP	SQ YD	39.0	39.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" ,N50	TON	3,368.0	2,685.0	683.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	18,176.0	18,176.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	21,438.0	13,309.0	8,129.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	598.0	598.0	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	7.0	7.0	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	6.0	6.0	
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	1.0	1.0	

PLOT DATE = 1/25/2008  
 FILE NAME = c:\pwworkspace\pwworkspace\10124582\10124582.dgn  
 PLOT SCALE = 42.3029 / IN.  
 USER NAME = bouchardj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. DATE  
 HORIZ. DATE

DRAWN BY  
 CHECKED BY