

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	122 RS-4	VERMILION	42	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

HMA SURFACE REMOVAL

	STATION	TO	STATION	LENGTH	WIDTH	AREA	40600982 HMA SURF. REM. BUTT JOINT (SQ YD)	44000155 HMA SURF. REM. 1 1/2" (SQ YD)	44000152 HMA SURF. REM. 3/4" (SQ YD)
	1282+10.00		1282+40.00	30.0	26.0	86.7	0.0	86.7	0.0
	1282+40.00		1284+78.00	238.0	26.0	687.6	0.0	687.6	0.0
	1284+78.00		1288+65.00	387.0	26.5	1139.5	0.0	1139.5	0.0
	1288+65.00		1328+04.00	3939.0	24.0	10504.0	0.0	10504.0	0.0
	1328+04.00		1390+95.70	6291.7	26.0	18176.0	0.0	0.0	18176.0
	1390+95.70		1391+25.70	30.0	26.0	86.7	86.7	0.0	0.0
	IL 9								
*	520+37.00		522+48.00	211.0	25.0	586.1	0.0	586.1	0.0
*	522+74.00		524+44.00	170.0	25.0	304.9	0.0	304.9	0.0
	PARKING LANES								
LT.	1288+26.00		1289+84.40	158.4	5.0	88.0	0.0	88.0	0.0
RT.	1288+25.00		1289+84.40	159.4	5.0	88.6	0.0	88.6	0.0
LT.&RT.	1289+84.40		1307+00.00	1715.6	9.0	3431.2	0.0	3431.2	0.0
LT.&RT.	1307+00.00		1314+05.00	705.0	11.0	1723.3	0.0	1723.3	0.0
LT.&RT.	1314+05.00		1326+54.00	1249.0	9.0	2498.0	0.0	2498.0	0.0
LT.&RT.	1326+54.00		1328+04.00	150.0	9.0	300.0	0.0	300.0	0.0
	TOTAL =						86.7	21437.9	18176.0
	USE =						87.0	21438.0	18176.0

*TURN AREAS ARE INCLUDED IN THIS
CALCULATION AND WERE MEASURED ON
CADD

SHEET 2 OF 6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE
OF
QUANTITIES**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 1/25/2010
FILE NAME = c:\p\p\work\p\11001\BUCKLES\11\40124902\planahs.dgn
PLOT SCALE = 42,362% / IN.
USER NAME = bucklesj