

SUMMARY OF QUANTITIES

FAT RURAL  
90% FEDERAL  
10% STATE

CODE NO.	ITEM	UNIT	TOTAL	X271-2A
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	180	180
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2250	2250
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	802	802
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1900	1900
78000200	* THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2000	2000
78003110	* PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	250	250
78100100	* RAISED REFLECTIVE PAVEMENT MARKER	EACH	28	28
78200100	* MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4
78200410	* GUARDRAIL MARKERS, TYPE A	EACH	16	16
78201000	* TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24
X0320870	BRACED EXCAVATION	CU YD	132	132
X0323583	SPEED INDICATOR SIGN	CAL DA	360	360
X0323830	DRAINAGE SCUPPER, DS-11	EACH	4	4
X5080600	MECHANICAL SPLICERS	EACH	104	104
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	70	70
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
Z0038700	PERMANENT BENCH MARKS	EACH	1	1
Z0050000	REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS	EACH	2	2

\* - SPECIALITY ITEM

HURST-ROSCHKE ENGINEERS, INC.  
HILLSBORO, ILLINOIS 62049  
(217)532-3959 FAX (217)532-3212



FILE NAME =	USER NAME = keyrb	DESIGNED - JJC	REVISED -
c:\p\work\FWIDOT\KEYSRB\d0164230\0570	50-shs-500.dgn	DRAWN - TWC	REVISED -
	PLOT SCALE = 10.0000' / IN.	CHECKED - MAR	REVISED -
	PLOT DATE = 2/1/2010	DATE - 01-27-10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6)HBR-5	CHAMPAIGN	63	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70750	