INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES
3	LOCATION MAP - FAS ROUTE 684 (CLINTON RD.)
4-5	EXISTING TYPICAL CROSS SECTIONS - FAS 684 (CLINTON RD.)
6	SUMMARY OF QUANTITIES
7-14	PATCHING SCHEDULE
15-18	PAVEMENT MARKING DETAILS (RURAL AND URBAN APPLICATIONS)

HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
442101-07	CLASS B PATCHES
701201-03	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE 2L, 2W, MOVING OPERATION - DAY ONLY
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
701301-03	

GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-442B -- PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST
INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING.
VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-780 SPECIAL

PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION
OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE WITH
THE EXISTING PAVEMENT MARKINGS. PAINT PAVEMENT MARKINGS SHALL BE LIMITED
TO ONLY THE LENGTH SEGMENTS ASSOCIATED WITH INDIVIDUAL PATCH LOCATIONS
AND SHALL NOT BE APPLIED CONTINUOUSLY THROUGH THE PROJECT
BETWEEN PATCH LOCATIONS.

G.N. - 783 SPECIAL

ANY RAISED REFLECTIVE PAVEMENT MARKERS THAT FALL IN TO A PATCH AREA ARE TO BE REMOVED AND SHALL NOT BE REPLACED. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR CLASS B PATCHES, TYPE 2, 8" AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

NO COMMITMENTS ASSOCIATED WITH PROJECT

							•
FILE NAME :	USER NAME = bucklesjj	DESIGNED -	REVISED -		GENERAL NOTES /INDEX OF SHEETS	F.A.S. SECTION	COUNTY TOTAL SHEET
c:\pw.work\PWIDOT\BUCKLESJJ\dØ176654\D	70817-Gennote.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		COA COOT	EDCAR 10 2
1	PLOT SCALE = 40.0000 '/ [N.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	HIGHWAY STANDARDS	604 6UF1	CONTRACT NO. 70817
	PLOT DATE = 1/15/2010	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS	FED. AID PROJECT