

STATION	DIRECTION	LENGTH	WIDTH	TYPE II			DOWEL BARS	SAW CUTS	TIE BARS	PAVEMENT FABRIC
				8.0"	8.0"	8.0"				
				44200934	44200942	44200944				
(ft)	(ft)	(sq. yd)	(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)		
5+18.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
8+17.00	SOUTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
8+17.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
10+35.00	SOUTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
10+35.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
11+77.00	SOUTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
11+77.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
15+20.00	SOUTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
15+20.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
22+28.00	SOUTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
22+28.00	NORTHBOUND	6	12	8.0	0.0	0.0	20	48.0	0	0.0
30+80.00	SOUTHBOUND	20	11	0.0	24.4	0.0	27	53.0	10	24.4
30+80.00	NORTHBOUND	20	11	0.0	24.4	0.0	27	53.0	10	24.4
42+26.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
42+26.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
61+35.00	NORTHBOUND	30	11	0.0	0.0	36.7	27	63.0	15	36.7
80+88.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
80+88.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
81+37.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
81+37.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
81+87.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
81+87.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
82+38.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
82+38.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
83+38.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
83+38.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
84+39.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
84+39.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
85+41.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
85+41.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
88+99.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
88+99.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
96+48.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
96+48.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
96+99.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
96+99.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
102+48.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
102+48.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
105+35.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	45.0	0	0.0
105+35.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	45.0	0	0.0
106+58.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
106+58.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
107+36.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
107+86.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
107+86.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
108+36.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
108+86.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0
108+86.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0

STATION	DIRECTION	LENGTH	WIDTH	TYPE II			DOWEL BARS	SAW CUTS	TIE BARS	PAVEMENT FABRIC	
				8.0"	8.0"	8.0"					
				44200934	44200942	44200944					
(ft)	(ft)	(ft)	(ft)	(sq. yd)	(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)	
108+99.00	NORTHBOUND	20	11	0.0	24.4	0.0	27	53.0	20	24.4	
110+09.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
110+09.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
112+60.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+04.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+39.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+69.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+69.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+88.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
113+88.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
114+65.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
115+61.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
115+61.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
117+08.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
117+84.00	SOUTHBOUND	20	11	0.0	24.4	0.0	27	53.0	10	24.4	
117+84.00	NORTHBOUND	20	11	0.0	24.4	0.0	27	53.0	10	24.4	
119+13.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
120+21.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
120+43.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
121+21.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
121+21.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
124+17.00	NORTHBOUND	35	11	0.0	0.0	42.8	36	68.0	18	42.8	
124+45.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
124+63.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
124+95.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
124+95.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
127+26.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	39.0	0	0.0	
128+47.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
128+98.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
129+32.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
129+32.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
136+26.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
137+20.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
137+20.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
140+20.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
140+20.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
143+28.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
143+28.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
144+18.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
144+18.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
144+71.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
144+71.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
145+77.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
146+28.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
146+28.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
158+19.00	SOUTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
158+19.00	NORTHBOUND	6	11	7.3	0.0	0.0	18	0.0	0	0.0	
				TOTAL=	652.7	122.2	79.4	1804.0	3159.0	93.0	201.6
				USE=	653.0	123.0	80.0	1804.0	3159.0	93.0	202.0

FILE NAME = c:\pwwork\pwwork\pwwork\00179880\70818 Schedules.dgn

USER NAME = bowerml
 PLOT SCALE = 40.0000 / IN.
 PLOT DATE = 1/21/2010

DESIGNED *DJC*
 DRAWN *MLB*
 CHECKED *MLB*
 DATE *1/04/2010*

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE

F.A.S. RTE. 331	SECTION (B1,15D)PT	COUNTY VERMILION	TOTAL SHEETS 11	SHEET NO. 7
CONTRACT NO. 70818				
ILLINOIS FED. AID PROJECT				