

## SCHEDULE OF QUANTITIES

### PATCHING SCHEDULE

STATION	DIRECTION	LENGTH	WIDTH	PATCH AREA		DOWEL BARS	SAW CUTS	TIE BARS	PAVEMENT FABRIC
				TYPE II	TYPE IV				
				14	14				
				(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)
27+38	EB	6	15	10.0	0.0	26	51.0	0	0.0
27+38	WB	6	15	10.0	0.0	26	51.0	0	0.0
39+80	WB	6	15	10.0	0.0	26	51.0	0	0.0
87+00	EB	6	15	10.0	0.0	26	51.0	0	0.0
87+00	WB	6	15	10.0	0.0	26	51.0	0	0.0
91+64	EB	6	15	10.0	0.0	26	51.0	0	0.0
91+64	WB	6	15	10.0	0.0	26	51.0	0	0.0
98+20	EB	6	15	10.0	0.0	26	51.0	0	0.0
98+20	WB	6	15	10.0	0.0	26	51.0	0	0.0
98+70	WB	6	15	10.0	0.0	26	51.0	0	0.0
105+83	EB	6	15	10.0	0.0	26	51.0	0	0.0
105+83	WB	6	15	10.0	0.0	26	51.0	0	0.0
106+87	WB	6	15	10.0	0.0	26	51.0	0	0.0
109+83	WB	6	15	10.0	0.0	26	51.0	0	0.0
110+55	EB	6	15	10.0	0.0	26	51.0	0	0.0
110+55	WB	6	15	10.0	0.0	26	51.0	0	0.0
110+85	EB	6	15	10.0	0.0	26	51.0	0	0.0
111+45	EB	6	15	10.0	0.0	26	51.0	0	0.0
111+45	WB	6	15	10.0	0.0	26	51.0	0	0.0
132+93	EB	6	15	10.0	0.0	26	51.0	0	0.0
132+93	WB	6	15	10.0	0.0	26	51.0	0	0.0
157+58	EB	40	15	0.0	66.7	52	85.0	20	66.7
157+58	WB	40	15	0.0	66.7	52	85.0	20	66.7
195+00	EB	6	15	10.0	0.0	26	51.0	0	0.0
195+00	WB	6	15	10.0	0.0	26	51.0	0	0.0
203+40	EB	20	15	0.0	33.3	39	65.0	10	33.3
203+40	WB	20	15	0.0	33.3	39	65.0	10	33.3
205+50	EB	6	15	10.0	0.0	26	51.0	0	0.0
205+50	WB	6	15	10.0	0.0	26	51.0	0	0.0
302+80	WB	6	15	10.0	0.0	26	51.0	0	0.0
316+80	EB	6	15	10.0	0.0	26	51.0	0	0.0
316+80	WB	6	15	10.0	0.0	26	51.0	0	0.0
360+90	WB	6	15	10.0	0.0	26	51.0	0	0.0
361+20	EB	6	15	10.0	0.0	26	51.0	0	0.0
361+60	EB	6	15	10.0	0.0	26	51.0	0	0.0
361+60	WB	6	15	10.0	0.0	26	51.0	0	0.0
FINAL TOTAL =				320.0	200.0	1,014	1932.0	60	200.0
				(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)
USE =				320.0	200.0	1,014	1932.0	60	200.0

FILE NAME =	USER NAME = ceerlockjd	DESIGNED - DWO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pwork\PWIDOT\CEARLOCKJD\0182178\0570823\sh\schedule.dgn		DRAWN - BBP	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	317	(27,28)PT	MCLEAN	5	5
		CHECKED -	REVISED -					CONTRACT NO. 70823				
		DATE - 01/26/10	REVISED -					ILLINOIS FED. AID PROJECT				