

SCHEDULE OF QUANTITIES

CLASS A PATCHING SCHEDULE, 13"

				44200574	44200610	44213200	44213000		
LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	TYPE I, 13" (SQ YD)	TYPE II, 13" (SQ YD)	SAW CUTS (FT)	PATCHING REINFORCEMENT (SQ YD)		
N.B. D.L.	650+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	90+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	160+00.00	10.00	12.00		13.33	68.00	13.33		
N.B. D.L.	165+00.00	6.00	6.00	4.00		36.00	4.00		
N.B. D.L.	170+00.00	6.00	6.00	4.00		36.00	4.00		
N.B. D.L.	240+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	297+00.00	10.00	12.00		13.33	68.00	13.33		
N.B. D.L.	340+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. P.L.	340+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	343+00.00	10.00	12.00		13.33	68.00	13.33		
N.B. D.L.	343+50.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	379+50.00	6.00	6.00	4.00		36.00	4.00		
N.B. D.L.	380+50.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	440+00.00	6.00	6.00	4.00		36.00	4.00		
N.B. D.L.	495+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	530+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	610+00.00	6.00	12.00		8.00	60.00	8.00		
N.B. D.L.	625+00.00	6.00	12.00		8.00	60.00	8.00		
S.B. D.L.	74+00.00	6.00	6.00	4.00		36.00	4.00		
S.B. D.L.	250+00.00	6.00	6.00	4.00		36.00	4.00		
S.B. D.L.	340+00.00	10.00	6.00		6.67	44.00	6.67		
S.B. D.L.	341+00.00	6.00	6.00	4.00		36.00	4.00		
S.B. D.L.	437+00.00	6.00	12.00		8.00	60.00	8.00		
S.B. D.L.	500+00.00	6.00	12.00		8.00	60.00	8.00		
S.B. D.L.	530+00.00	6.00	12.00		8.00	60.00	8.00		
S.B. D.L.	605+00.00	6.00	12.00		8.00	60.00	8.00		
S.B. D.L.	620+00.00	6.00	12.00		8.00	60.00	8.00		
TOTAL =				28.00	174.66	1460.00	202.66		
USE =				28.00	175.00	1460.00	203.00		
				(SQ YD)	(SQ YD)	(FT)	(SQ YD)		

NOTE:
 THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.
 THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED IN G.N.-442B.

44000162 HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
N.B. D.L.	587+34.90		751+72.66	16437.76	12.00	21917.01
N.B. P.L.	587+34.90		751+72.66	16437.76	12.00	21917.01
N.B. D.L.	756+24.38		783+30.73 (BK)	2706.35	12.00	3608.47
N.B. P.L.	756+24.38		783+30.73 (BK)	2706.35	12.00	3608.47
N.B. D.L.	74+89.65 (AH)		252+74.34 (BK)	17784.69	12.00	23712.92
N.B. P.L.	74+89.65 (AH)		252+74.34 (BK)	17784.69	12.00	23712.92
N.B. D.L.	252+87.76 (AH)		295+46.45	4258.69	12.00	5678.25
N.B. P.L.	252+87.76 (AH)		295+46.45	4258.69	12.00	5678.25
N.B. D.L.	300+06.95		339+58.65	3951.70	12.00	5268.93
N.B. P.L.	300+06.95		339+58.65	3951.70	12.00	5268.93
N.B. D.L.	345+03.35		381+37.19 (BK)	3633.84	12.00	4845.12
N.B. P.L.	345+03.35		381+37.19 (BK)	3633.84	12.00	4845.12
N.B. D.L.	376+50.00 (AH)		500+76.00	12426.00	12.00	16568.00
N.B. P.L.	376+50.00 (AH)		500+76.00	12426.00	12.00	16568.00
N.B. D.L.	500+76.00		603+77.75	10301.75	12.00	13735.67
N.B. P.L.	500+76.00		603+77.75	10301.75	12.00	13735.67
N.B. D.L.	603+77.75		647+48.69	4370.94	12.00	5827.92
N.B. P.L.	603+77.75		647+48.69	4370.94	8.00	746.67
N.B. P.L.	612+17.75		637+16.72	2498.97	12.00	3331.96
N.B. A.L.	603+77.75		647+48.69	4370.94	12.00	5827.92
N.B. A.L.	637+16.72		642+89.44	572.72	20.00	1272.71
N.B. P.L.	642+89.44		647+48.69	459.25	12.00	612.33
N.B. A.L.	642+89.44		647+48.69	459.25	12.00	612.33
N.B. GORE	642+89.44		647+48.69	459.25	8.00	408.22
S.B. D.L.	587+34.90		750+70.82	16335.92	12.00	21781.23
S.B. P.L.	587+34.90		750+70.82	16335.92	12.00	21781.23
S.B. D.L.	755+34.40		783+30.73 (BK)	2796.33	12.00	3728.44
S.B. P.L.	755+34.40		783+30.73 (BK)	2796.33	12.00	3728.44
S.B. D.L.	74+89.65 (AH)		252+74.34 (BK)	17784.69	12.00	23712.92
S.B. P.L.	74+89.65 (AH)		252+74.34 (BK)	17784.69	12.00	23712.92
S.B. D.L.	252+87.76 (AH)		295+33.23	4245.47	12.00	5660.63
S.B. P.L.	252+87.76 (AH)		295+33.23	4245.47	12.00	5660.63
S.B. D.L.	299+96.23		338+93.99	3897.76	12.00	5197.01
S.B. P.L.	299+96.23		338+93.99	3897.76	12.00	5197.01
S.B. D.L.	344+38.69		381+37.19 (BK)	3698.50	12.00	4931.33
S.B. P.L.	344+38.69		381+37.19 (BK)	3698.50	12.00	4931.33
S.B. D.L.	376+50.00 (AH)		500+76.00	12426.00	12.00	16568.00
S.B. P.L.	376+50.00 (AH)		500+76.00	12426.00	12.00	16568.00
S.B. D.L.	500+76.00		659+50.14	15874.14	12.00	21165.52
S.B. P.L.	500+76.00		659+50.14	15874.14	12.00	21165.52
S.B. A.L.	613+90.99		620+90.99	700.00	7.00	544.44
S.B. A.L.	620+90.99		636+90.99	1600.00	12.00	2133.33
S.B. A.L.	636+90.99		648+11.82	1120.83	18.00	2241.66
S.B. GORE	639+90.99		645+90.99	600.00	4.00	266.67
S.B. GORE	645+90.99		648+11.82	220.83	10.00	245.37

TOTAL = 420230.44 SQ YD
USE = 420230.00 SQ YD

LEGEND FOR SCHEDULE OF QUANTITIES			
N.B.	NORTHBOUND	D.L.	DRIVING LANE
S.B.	SOUTHBOUND	P.L.	PASSING LANE
C.L.	CENTERLINE	A.L.	AUXILIARY LANE