

SCHEDULE OF QUANTITIES

HOT MIX ASPHALT SCHEDULE

STATION TO	STATION	LENGTH (FOOT)	TOTAL WIDTH (FOOT)	AREA (SQ YD)	HMA SC THICKNESS (INCH)	HMA BC THICKNESS (INCH)	40603550 P HMA SC MIX "D" N 105 (TON)	40603245 P HMA BC IL 19.0 N 105 (TON)	40603525 P HMA SC MIX "C" N 105 (TON)	40600100 BIT MATLS PR CT (GAL)	40600300 AGG PR CT (TON)	X0322729 MATERIAL TRANSFER DEVICE (TON)	
781+58	- 919+00 (EB DL)	13742	12	18323		6.0"		6158				6158	
919+00	- 1035+00 (EB DL)	11800	12	15467		7.5"		6497				6497	
781+58	- 1035+00 (EB DL)	25342	28	78842	1.5"		6625			23655	158	6625	
100+00	- 375+88 (EB & WB DL)	27588	28	85830	1.5"		7210			17166	172	6180	
100+00	- 375+88 (WB DL)	27588	12	36784		3.5"		7210				7210	
100+00	- 375+88 (EB DL)	27588	12	36784	1.75"							3605	
TOTAL								13835	19865	3605	40821	330	36275

HMA SURFACE REMOVAL SCHEDULE

STATION TO	STATION	LENGTH	WIDTH	AREA	44000155 HMA SURF REMOVAL 1 1/2 INCHES (SQ YD)	44000162 HMA SURF REMOVAL 3 1/4 INCHES (SQ YD)	44000169 HMA SURF REMOVAL 5 INCHES (SQ YD)	44000198 HMA SURF REMOVAL VARIABLE DEPTH (SQ YD)
781+58	- 1035+00 (EB PL)	25342	16	45053	45053			
781+58	- 1035+00 (EB DL)	25342	12	33790				33790
375+88	- 100+00 (EB & WB PL SHLDR)	27588	4	12262	12262			
375+88	- 100+00 (EB DL)	27588	12	36784		36784		
375+88	- 100+00 (WB DL)	27588	12	36784			36784	
TOTAL					57315	36784	36784	33790

TEMPORARY RAMP SCHEDULE

STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	40600990 TEMP RAMP (SQ YD)
781+58 (DL + PL + Shldrs)	5	28	15.5	15.5
1035+00 (DL + PL + Shldrs)	5	28	15.5	15.5
100+00 (EB & WB DL)	5	24	13.5	13.5
375+88 (EB & WB DL)	5	24	13.5	13.5
TOTAL				58.0

PAVEMENT MARKING SCHEDULE

STATION TO	STATION	LENGTH	78000200 THERMOPLASTIC PAVEMENT MARKING LINE 4		78000500 THERMO PVT MKG LINE 8 WHITE (FT)	PREFMD PLASTIC PVT MKG TY B 4" (FT)
			WHITE (FT)	YELLOW (FT)		
781+58	- 1035+00 (EB)	25342	25342	25342		6336
100+00	- 375+88 (EB & WB)	27588	55176	55176	1500	13794
SUB-TOTAL			80518	80518		
TOTAL			161036		1500	20130
USE			161050			

AERIAL SPEED CHECK MARKING

STATIONS:	910+02	18" White	12 Ft
	916+62	18" White	12 Ft
TOTAL			24.0 Foot

*See D5 Detail of Pavement Marking for Additional Requirements.