

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	86-11LS	SCOTT	19	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Y003  
100%  
STATE

INDEX

- 1 COVER SHEET, STANDARDS
- 2 INDEX, SUMMARY OF QUANTITIES, GENERAL NOTES
- 3-19 LANDSCAPING PLANS

GENERAL NOTES

1. THE TREES SHALL BE SPACED A MINIMUM OF 20 FEET APART.
2. THE LOCATIONS OF ALL PLANTS SHOWN ON THE PLANS ARE APPROXIMATE. THE DISTRICT LANDSCAPE ARCHITECT AND THE DEPARTMENT SHALL HAVE THE RIGHT TO ADJUST THE LOCATION OF PLANTS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED THE CONTRACTOR FOR CONFORMING WITH THIS PROVISION.
3. CLASS 4 SEEDING AREAS SHALL EXTEND FROM A LINE 20 FEET FROM THE EDGES OF THE OUTSIDE SHOULDERS TO THE ACCESS CONTROL OR THE RIGHT-OF-WAY LINES AT THE LOCATIONS SHOWN ON THE PLANS.
4. THE SEEDING SHALL NOT BEGIN UNTIL ALL OTHER WORK HAS BEEN COMPLETED ON THIS SECTION UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT OR THE ENGINEER. NO FERTILIZER NUTRIENTS OR MULCH WILL BE REQUIRED FOR THE INTER SEEDING.
5. THE CONSTRUCTION LIMITS SHOWN ON THE PLANS ARE FOR THE GRADING AND PAVING OF THE VARIOUS CONSTRUCTION SECTIONS AND SHALL NOT BE CONSTRUED TO BE THE LIMITS FOR THE LANDSCAPING ON THIS PROJECT.

COMMITMENTS

SUMMARY OF QUANTITIES

PAY CODE ITEM	ITEM	UNIT	TOTAL	QUANTITY PER SHEET																	
				3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	
25000750	MOWING	ACRE	17.6					0.3	4.6	3.9	0.3					3.9	1.3	1.6	1.7		
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	17.6					0.3	4.6	3.9	0.3					3.9	1.3	1.6	1.7		
67100100	MOBILIZATION	L SUM	1.0																		
A2001020	TREE, ACER RUBRUM (RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	53	2	3	5	3	2	2	4	7		5		3	6	3	2	5	2	
A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	64	3	5	6		7	8	7	8		5		3	4	3		3	2	
A2002320	TREE, BETULA NIGRA (RIVER BIRCH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8			2	2			2								2			
A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	20		2		2		4	5			3	2		2					
A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	28		3	2		2	3	5	3			2		2		3		3	
A2007720	TREE, TAXODIUM DISTICHUM SHAWNEE BRAVE (SHAWNEE BRAVE BALD CYPRESS), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9							6				3							
B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	18					4	2				2		2	3			2	3	
B2001666	TREE, CRATAEGUS CRUGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	9										2		3	2		2			
B2001966	TREE, CRATAEGUS PHAENOPYRUM (WASHINGTON HAWTHORN), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5			3	2														
B2003066	TREE, MALUS BRANDYWINE (BRANDYWINE CRAB APPLE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	17	2		2		2	4				3					2	2		
B2004316	TREE, MALUS RADIANT (RADIANT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	22						3				3	2	3	2	3			3	
B2005066	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	25		2	2	2	5	4	2		2			3	3					
D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	55		10	5		5					5	5		5	5	5	10		
K0026700	TREE CARE	EACH	2																		
K0026710	TREE CARE MULCH	L SUM	1																		
K0026720	TREE INTERMEDIATE AND SHRUB WATERING	UNIT	4																		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
INDEX, SUMMARY OF QUANTITIES,  
 AND GENERAL NOTES  
 FAP ROUTE 310  
 SCALE: VERT.      DRAWN BY    EMR  
 HORIZ.              CHECKED BY   WTS  
 DATE