

SEEDING SCHEDULE

LOCATION (STATION TO STATION)	SEEDING CLASS 2	FERTILIZER NUTRIENTS			AG LIME	MULCH METH - 2
		NITR.	PHOS.	POTAS.		
	(ACRE)	(POUND)	(POUND)	(POUND)	(TON)	(ACRE)
<u>ALIGNMENT A001</u> 27+50 TO 120+00	2.5	225	225	225	5.0	2.5
<u>ALIGNMENT B001</u> 324+17 TO 348+00	1.0	90	90	90	2.0	1.0
TOTAL =	3.5	315.0	315.0	315.0	7.0	3.5

ESTIMATED QUANTITIES

ITEMS	UNIT	TOTAL
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HAUL ROAD REPAIRS (SEE SPECIAL PROVISIONS)		
BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	270
SEAL COAT AGGREGATE	TON	1,700
CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	100
CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100
CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HANDLING TEMPORARY EROSION CONTROL (SEE SPECIAL PROVISIONS)		
TEMPORARY EROSION CONTROL SEEDING	POUND	700

• LAGRANGE WETLAND BANK
•• D6 WETLAND MITIGATION NO.4