

ROADWAY SCHEDULE

LOCATION	GRADING AND SHAPING ROADWAY ( UNIT )	SUB-BASE GRAN. T-B 4" THICK ( TON )	AGG. SURF. T-A 2" THICK ( TON )
<u>ALIGNMENT A001g</u>			
STA 27+50 TO STA 120+00	93	3910.0	1895.0
RT STA 37+00 ( FIELD ENTRANCE 50' LONG )			40.0
LT STA 42+00 ( FIELD ENTRANCE 50' LONG )			40.0
RT STA 42+00 ( FIELD ENTRANCE 50' LONG )			40.0
LT STA 47+00 TO STA 48+00 ( PARKING LOT )		76.0	38.0
LT STA 56+00 ( FIELD ENTRANCE 50' LONG )			40.0
RT STA 56+00 ( FIELD ENTRANCE 50' LONG )			40.0
LT STA 74+00 ( FIELD ENTRANCE 60' LONG )			46.0
RT STA 74+00 ( FIELD ENTRANCE 70' LONG )			53.0
RT STA 76+00 TO STA 77+00 ( PARKING LOT )		76.0	38.0
LT STA 78+00 ( FIELD ENTRANCE 60' LONG )			46.0
RT STA 78+00 ( FIELD ENTRANCE 70' LONG )			53.0
RT STA 100+00 TO STA 101+00 ( PARKING LOT )		76.0	38.0
RT STA 115+00 TO STA 117+88 ( PARKING LOT & CUL-DE-SAC )		360.0	180.0
LT STA 117+00 ( FIELD ENTRANCE 70' LONG )			53.0
<u>ALIGNMENT B001</u>			
STA 324+17 TO STA 348+00	24	1012.0	490.0
RT STA 323+62 TO STA 326+10 ( PARKING LOT & CUL-DE-SAC )		340.0	170.0
RT STA 330+00 ( FIELD ENTRANCE 50' LONG )			40.0
RT STA 333+50 ( FIELD ENTRANCE 50' LONG )			40.0
<b>TOTAL =</b>	<b>117</b>	<b>5850.0</b>	<b>3380.0</b>

• LAGRANGE WETLAND BANK  
•• D6 WETLAND MITIGATION NO.4

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwork\PWIDOT\LAUGHLINRL\dms28174\tsch.dgn		DRAWN - EJW	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - JCN	REVISED -
	PLOT DATE = Feb-03-2010 04:29:23PM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	BROWN	37	6
CONTRACT NO. 72968			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	