

SUMMARY OF QUANTITIES				STATE 100%
				I000
CODE NO	ITEM	UNIT	TOTAL	TOTAL
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	20.0	20.0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.2	32.2
40600300	AGGREGATE (PRIME COAT)	TON	120.6	120.6
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1758.1	1758.1
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	745.0	745.0
40600990	TEMPORARY RAMP	SQ YD	27.0	27.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3529.7	3529.7
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	88.4	88.4
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	42407.0	42407.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1442.1	1442.1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	6.0
67100100	MOBILIZATION	LSUM	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4752.0	4752.0
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	39184.0	39184.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	528.0	528.0
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	39184.0	39184.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	198.0	198.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	198.0	198.0

\*Specialty Hems

FILE NAME =	USER NAME = laughtlrv1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pv\work\PWIDOT\LAUHLINRL\dms26774\672645-sh1-S00.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	658	HRS-1, GRS-5)	MASON	15 3
PLOT SCALE = 100.0000 ' / IN.		CHECKED -	REVISED -		CONTRACT NO. 72A45									
PLOT DATE = Feb-03-2010 09:54:18AM		DATE -	REVISED -		ILLINOIS FED. AID PROJECT									