



2CC:
85' - 500'
ϕ = 9.0'

2CC:
110' - 400'
ϕ = 15.0'

2CC:
60' - 200'
ϕ = 5.0'

2CC:
45' - 300'
ϕ = 10.0'

**FAP 67 (IL 125)
ALIGNMENT**

(A) 159+50.00, ♂ ELEV.= 625.13	(O) 162+50.00, 21.02' LT ELEV.= 625.32
(B) 160+00.00, ♂ ELEV.= 625.21	(P) 163+00.00, 18.00' LT ELEV.= 625.45
(C) 160+50.00, ♂ ELEV.= 625.30	(Q) 159+50.00, 18.00' RT ELEV.= 624.86
(D) 161+00.00, ♂ ELEV.= 625.38	(R) 160+00.00, 18.00' RT ELEV.= 624.94
(E) 161+50.00, ♂ ELEV.= 625.47	(S) 160+50.00, 18.00' RT ELEV.= 625.03
(F) 162+00.00, ♂ ELEV.= 625.55	(T) 161+00.00, 18.00' RT ELEV.= 625.11
(G) 162+50.00, ♂ ELEV.= 625.64	(U) 161+50.00, 18.00' RT ELEV.= 625.20
(H) 163+00.00, ♂ ELEV.= 625.72	(V) 162+00.00, 18.00' RT ELEV.= 625.28
(I) 159+50.00, 18.00' LT ELEV.= 624.86	(W) 162+50.00, 24.69' RT ELEV.= 625.27
(J) 160+00.00, 20.54' LT ELEV.= 624.90	(X) 163+00.00, 18.28' RT ELEV.= 625.44
(K) 160+50.00, 28.16' LT ELEV.= 624.87	(Y) 160+94.61, 50.75' LT ELEV.= 625.04
(L) 161+00.00, 18.00' LT ELEV.= 625.11	(GG) 162+05.29, 43.41' LT ELEV.= 625.28
(M) 161+50.00, 18.00' LT ELEV.= 625.20	(PP) 161+47.57, 31.87' RT ELEV.= 624.92
(N) 162+00.00, 18.00' LT ELEV.= 625.28	

**FAS 1573 (IL 123)
ALIGNMENT**

(Z) 248+00.00, 22.91' RT ELEV.= 625.20
(AA) 248+00.00, ♂ ELEV.= 625.54
(BB) 248+00.00, 22.29' LT ELEV.= 625.21
(CC) 247+50.00, 13.00' RT ELEV.= 625.40
(DD) 247+50.00, ♂ ELEV.= 625.59
(EE) 247+50.00, 14.60' LT ELEV.= 625.37
(FF) 248+50.00, ♂ ELEV.= 625.34
(HH) 248+24.45, 28.47' LT ELEV.= 625.24

**TR 22 (YANKEETOWN RD.)
ALIGNMENT**

(II) 8+75.00, 9.60' LT. ELEV.= 624.35
(JJ) 8+75.00, ♂ ELEV.= 624.49
(KK) 8+75.00, 9.43' RT ELEV.= 624.35
(LL) 9+00.00, 9.97' LT ELEV.= 624.30
(MM) 9+00.00, ♂ ELEV.= 624.45
(NN) 9+00.00, 9.84' RT ELEV.= 624.30
(OO) 9+50.00, ♂ ELEV.= 624.69
(QQ) 9+26.63, 11.53' LT ELEV.= 624.31
(RR) 9+44.95, 26.54' RT ELEV.= 624.15

FILE NAME =	USER NAME = coxte	DESIGNED - TMJ	REVISED - RTS 11-19-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 125 /IL 123 INTERSECTION ELEVATION DETAIL	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwid\COXTE\dms84394\sh125.dgn	PLOT SCALE = 40,0000' / IN.	DRAWN - TMJ	REVISED -			67	105(RS-6), 105(RS-4)		88	52
PLOT DATE = Dec-18-2009 04:49:41PM	DATE - 08-28-06	CHECKED - JCN	REVISED -			CONTRACT NO. T2C49				
		DATE - 08-28-06	REVISED -			ILLINOIS FED. AID PROJECT				