

Thermoplastic and Preformed Plastic Pavement Marking

Sta	to	Sta	Thermoplastic				Preformed			
			5" White (ft)	5" Yellow (ft)	6" White (ft)	8" White (ft)	12" White (ft)	12" Yellow (ft)	Letter & Symbols (sq ft)	24" White (ft)
<u>IL 29</u>										
328+82		315+30	2414	4494	224		230	62.4	83	
<u>Andrew Rd</u>										
100' East		100' West	427	194		138	60		45	
			2841	4688	224	138	60	230	62.4	128

Pavement Marking Removal

Location	(sq ft)	(sq ft)	(sq ft)	(sq ft)	(sq ft)	(sq ft)	(sq ft)	(sq ft)
IL 29 and Andrew Rd	2841	4688	224	138	60	230		128
	x5/12	x5/12	x6/12	x8/12	x12/12	x12/12		x2
	1184	1953	112	92	60	230	62.4	256

Total = 3950 sq ft

Remove Sign Panel Assy A, Relocate Sign Panel Assy A

Location	Quantity	Location	Quantity
Remove	(EA)	Relocate	(EA)
108+18 - SBL	1		
203+87 - NBL	1		
207+33 - SBL	1		
295+00 - NBL	1	296+49 - NBL	1
336+19 - SBL	1		
	5 total		1 total