

100%
STATE

LOCATION OF WORK				CONSTRUCTION TYPE CODE SECTION 84-1-2WS-4
SUMMARY OF QUANTITIES				WEIGH STATION
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	Y222
20200100	EARTH EXCAVATION	CU YD	4,874	4,874
20800150	TRENCH BACKFILL	CU YD	172	172
25000200	SEEDING, CLASS 2	ACRE	1.6	1.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	144	144
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	144	144
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	144	144
25100115	MULCH, METHOD 2	ACRE	1.6	1.6
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	1.6	1.6
28000305	TEMPORARY DITCH CHECKS	FOOT	90	90
28000400	PERIMETER EROSION BARRIER	FOOT	80	80
28000500	INLET ^{AND} PIPE PROTECTION	EACH	8	8
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	20	20
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	8,123	8,123
30201500	LIME	TON	163	163
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	105	105
31200100	STABILIZED SUB-BASE 4"	SQ YD	8,046	8,046
42000531	PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2" (JOINTED)	SQ YD	7,585	7,585
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	880	880
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	310	310
42400800	DETECTABLE WARNINGS	SQ FT	8.0	8.0
44000100	PAVEMENT REMOVAL	SQ YD	2,127	2,127
44000205	HOT-MIX ASPHALT PAVED SHOULDER REMOVAL	SQ YD	1,155	1,155
48101200	AGGREGATE SHOULDERS, TYPE B	TON	795	795
50102500	CONCRETE REMOVAL (SPECIAL)	CU YD	3.0	3.0
50105220	PIPE CULVERT REMOVAL	FOOT	139	139
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	61	61
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	12	12
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	96	96
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	96	96
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	240	240
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1

100%
STATE

LOCATION OF WORK				CONSTRUCTION TYPE CODE SECTION 84-1-2WS-4
SUMMARY OF QUANTITIES				WEIGH STATION
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	Y222
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	2	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	215	215
67100100	MOBILIZATION	L SUM	1	1
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1	1
72000100	SIGN PANEL-TYPE 1	SQ FT	2	2
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	12	12
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	5	5
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	341	341
81013200	CONDUIT IN TRENCH, 6" DIA., PVC	FOOT	244	244
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	53	53
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	993	993
81603030	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,105	1,105
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,532	1,532
81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	365	365
82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	6	6
83062740	LIGHT POLE, WEATHERING STEEL, 50 FT. M.M., TENON MOUNT	EACH	6	6
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	6	6
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	4	4
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	5	5
84200904	REMOVAL OF POLE FOUNDATION	EACH	5	5
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
X0323407	FLAG POLES	EACH	3	3
X0932150	CURB AND GUTTER OUTLET, SPECIAL	EACH	2	2
X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	3,611	3,611
X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	640	640
X8950200	REBUILD EXISTING HANDHOLE	EACH	1	1
X0326878	SEEPAGE FIELD MODIFICATIONS	L SUM	1	1

*Specialty Hems

Rev 1

FILE NAME =	USER NAME = laughlinr1	DESIGNED - ERB	REVISED - DRR 02/22/10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
si:\pwork\PIWIDOT\LAUGHLINRL\d8187896	dj0881_Sum.dgn	DRAWN - JJ	REVISED -			55	84-1-2WS-4	SANGAMON	36	3	
PLOT SCALE = 48.0000' / IN.		CHECKED - PJM	REVISED -			CONTRACT NO. 72058					
PLOT DATE = Feb-23-2010 11:38:27AM		DATE - 11/27/06	REVISED -			ILLINOIS FED. AID PROJECT					