

| PREFORMED PLASTIC PAVEMENT MARKING<br>TYPE B LETTERS AND SYMBOLS |          |
|--|----------|
| STATION - HANDICAPPED SYMBOL                                     | SQ FT    |
| 23+39 RT   | 5        |
| <b>TOTAL</b>   | <b>5</b> |

| URETHANE PAVEMENT MARKING - LINE 5" |                 |        |              |
|-------------------------------------|-----------------|--------|--------------|
| STATION                             | TO STATION      | COLOR  | FOOT         |
| 19+28.77 RT                         | 19+52.00 RT     | YELLOW | 38           |
| 19+28.77 RT                         | RPC 19+77.77 RT | YELLOW | 134          |
| RPC 19+77.77 RT                     | RPC 20+54.05 RT | YELLOW | 79           |
| RPC 20+54.05 RT                     | RPC 20+78.32 RT | YELLOW | 25           |
| RPC 20+78.32 RT                     | RPC 26+18.78 RT | YELLOW | 541          |
| RPC 26+18.78 RT                     | 27+01.30 RT     | YELLOW | 187          |
| 19+54.47 RT                         | 20+50.00 RT     | WHITE  | 110          |
| 19+54.47 RT                         | RPC 20+10.51 RT | WHITE  | 107          |
| RPC 20+10.51 RT                     | RPC 22+09.72 RT | WHITE  | 206          |
| RPC 22+09.72 RT                     | RPC 22+38.52 RT | WHITE  | 27           |
| RPC 22+38.52 RT                     | 23+35.48 RT     | WHITE  | 97           |
| 24+63.00 RT                         | 25+10.00 RT     | WHITE  | 55           |
| 24+55.00 RT                         | 24+74.00 RT     | YELLOW | 28           |
| 24+63.00 RT                         | 24+38.09 RT     | WHITE  | 33           |
| RPC 24+38.09 RT                     | RPC 24+42.90 RT | WHITE  | 41           |
| RPC 24+42.90 RT                     | RPC 25+18.67 RT | WHITE  | 83           |
| RPC 25+18.67 RT                     | RPC 25+99.31 RT | WHITE  | 84           |
| RPC 25+99.31 RT                     | RPC 26+17.80 RT | WHITE  | 19           |
| 26+15.00 RT                         | 26+77.32 RT     | WHITE  | 77           |
| RPC 26+17.80 RT                     | 26+77.32 RT     | WHITE  | 128          |
| 26+82.59 RT                         | 27+05.00 RT     | YELLOW | 33           |
| SCALE BUILDING CAR STALLS 7@20'     |                 | YELLOW | 218          |
| TRUCK PARKING STALLS 7@115'         |                 | YELLOW | 805          |
| PAINTED TRUCK ISLAND                |                 | YELLOW | 396          |
| SCALE BUILDING HANDICAP BLOCKOUT    |                 | YELLOW | 60           |
| <b>TOTAL</b>                        |                 |        | <b>3,611</b> |

| URETHANE PAVEMENT MARKING - LINE 12" |            |
|--------------------------------------|------------|
| LOCATION                             | FOOT       |
| SCALE BUILDING PARKING BLOCKOUT      | 170        |
| TRUCK PARKING PAINTED ISLAND         | 470        |
| <b>TOTAL</b>                         | <b>640</b> |

| COMBINATION CONCRETE<br>CURB AND GUTTER OUTLET, SPECIAL |          |
|---|----------|
| STATION   | EACH     |
| 22+38.52  | 1        |
| 24+35.16  | 1        |
| <b>TOTAL</b>  | <b>2</b> |

| SEEPAGE FIELD MODIFICATIONS |            |          |
|-----------------------------|------------|----------|
| STATION                     | TO STATION | L SUM    |
| 22+08 RT                    | 22+78 RT   | 1        |
| <b>TOTAL</b>                |            | <b>1</b> |

| FLAG POLES   |          |
|--------------|----------|
| STATION      | EACH     |
| 22+83 RT     | 1        |
| 22+89 RT     | 1        |
| 22+96 RT     | 1        |
| <b>TOTAL</b> | <b>3</b> |

| EARTH EXCAVATION   |                      |                |   |  |
|--------------------|----------------------|----------------|---|--|
| LOCATION           | RAW EARTH EXCAVATION | RAW EMBANKMENT | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) | EARTH EXCAVATION WASTE (+) OR BORROW (-) |
| STATION TO STATION | CU YD                | CU YD          | CU YD   | CU YD                                    |
| 15+30 RT 27+65 RT  | 4,874                | 3,374          | 3,656   | +282                                     |

| CONDUIT IN TRENCH, 2" DIA. PVC |                   |            |
|--------------------------------|-------------------|------------|
| STATION                        | TO STATION        | FOOT       |
| 22+87.15 RT                    | 23+31.2 RT        | 80         |
| 23+31.2 RT                     | 24+44 RT          | 111        |
| 25+79.88/ 118' RT              | 25+79.88/ 169' RT | 50         |
| <b>TOTAL</b>                   |                   | <b>241</b> |

| CONDUIT IN TRENCH, 6" DIA. PVC |            |            |
|--------------------------------|------------|------------|
| STATION                        | TO STATION | FOOT       |
| 23+00 RT                       | 22+70 RT   | 122        |
| 23+00 RT                       | 22+70 RT   | 122        |
| <b>TOTAL (FOR FUTURE USE)</b>  |            | <b>244</b> |

| CONDUIT AUGERED, 2" DIA. PVC |                  |            |
|------------------------------|------------------|------------|
| STATION                      | TO STATION       | FOOT       |
| 19+13.47 RT                  | 19+63.09 RT      | 48         |
| 21+16.35/ 12' RT             | 21+16.35/ 49' LT | 57         |
| 26+58.9 RT                   | 27+02.96 RT      | 48         |
| <b>TOTAL</b>                 |                  | <b>153</b> |

| UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-YPE USE), 3/4" DIA. POLYETHYLENE |            |            |
|--|------------|------------|
| STATION  | TO STATION | FOOT       |
| 20+73 RT   | 23+18 RT   | 252        |
| 21+06 RT   | 23+42 LT   | 313        |
| 23+18 RT   | 25+63 RT   | 251        |
| 25+63 RT   | 25+51 RT   | 177        |
| <b>TOTAL</b>   |            | <b>993</b> |

| UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-YPE USE), 1" DIA. POLYETHYLENE |            |              |
|--|------------|--------------|
| STATION  | TO STATION | FOOT         |
| 18+70.37 RT  | 21+06 RT   | 276          |
| 21+06 RT   | 23+31.2 RT | 326          |
| 23+31.2 RT   | 25+51 RT   | 256          |
| 25+51 RT   | 27+57.8 RT | 247          |
| <b>TOTAL</b>   |            | <b>1,105</b> |

| TRENCH AND BACKFILL WITH SCREENINGS OR SAND |                |            |
|---|----------------|------------|
| STATION                                     | TO STATION     | FOOT       |
| 22+85 RT                                    | 23+31.2 RT     | 80         |
| 23+00 RT                                    | 23+70 RT       | 122        |
| 23+31.2 RT                                  | 24+45 RT       | 115        |
| 25+81/ 168' RT                              | 25+81/ 120' RT | 48         |
| <b>TOTAL</b>                                |                | <b>365</b> |

| TRENCH AND BACKFILL FOR ELECTRICAL WORK |             |              |
|---|-------------|--------------|
| STATION                                 | TO STATION  | FOOT         |
| 18+70.37 RT                             | 19+13.37 RT | 40           |
| 19+62.49 RT                             | 21+06 RT    | 140          |
| 21+06 RT                                | 21+16.35 RT | 18           |
| 21+16.35 RT                             | 23+42 LT    | 225          |
| 21+06 RT                                | 22+85 RT    | 220          |
| 24+45 RT                                | 25+51 RT    | 110          |
| 20+73 RT                                | 23+18 RT    | 245          |
| 23+18 RT                                | 25+63 RT    | 245          |
| 25+63 RT                                | 25+51 RT    | 115          |
| 25+51 RT                                | 26+58.9 RT  | 114          |
| 27+02.96 RT                             | 27+57.8 RT  | 60           |
| <b>TOTAL</b>                            |             | <b>1,532</b> |

| LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT |          |
|--|----------|
| STATION  | EACH     |
| 20+73 RT                                       | 1        |
| 21+06 RT                                       | 1        |
| 23+18 RT                                       | 1        |
| 23+42 LT                                       | 1        |
| 25+51 RT                                       | 1        |
| 25+63 RT                                       | 1        |
| <b>TOTAL</b>                                   | <b>6</b> |

| LIGHT POLE, WEATHERING STEEL, 50 FT. M.H., TENON MOUNT |          |
|--|----------|
| STATION  | EACH     |
| 20+73 RT   | 1        |
| 21+06 RT   | 1        |
| 23+18 RT   | 1        |
| 23+42 LT   | 1        |
| 25+51 RT   | 1        |
| 25+63 RT   | 1        |
| <b>TOTAL</b>   | <b>6</b> |

| LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8' |          |
|---|----------|
| STATION   | EACH     |
| 20+73 RT  | 1        |
| 21+06 RT  | 1        |
| 23+18 RT  | 1        |
| 23+42 LT  | 1        |
| 25+51 RT  | 1        |
| 25+63 RT  | 1        |
| <b>TOTAL</b>  | <b>6</b> |

| BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN |          |
|---|----------|
| STATION   | EACH     |
| 23+42 LT  | 4        |
| <b>TOTAL</b>  | <b>4</b> |

| REMOVAL OF LIGHTING UNIT, SALVAGE |          |
|-----------------------------------|----------|
| STATION                           | EACH     |
| 21+98.2 RT                        | 1        |
| 22+22.52 RT                       | 1        |
| 23+17.30 LT                       | 1        |
| 24+12.9 RT                        | 1        |
| 24+15.05 RT                       | 1        |
| <b>TOTAL</b>                      | <b>5</b> |

| REMOVAL OF POLE FOUNDATION, CONCRETE |          |
|--------------------------------------|----------|
| STATION                              | EACH     |
| 21+98.2 RT                           | 1        |
| 22+22.52 RT                          | 1        |
| 23+17.30 LT                          | 1        |
| 24+12.9 RT                           | 1        |
| 24+15.05 RT                          | 1        |
| <b>TOTAL</b>                         | <b>5</b> |

| REBUILD EXISTING HANDHOLE |          |
|---------------------------|----------|
| STATION                   | EACH     |
| 23+22.86 RT               | 1        |
| <b>TOTAL</b>              | <b>1</b> |