

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE X071-2A			CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE X071-2A		
20200100	EARTH EXCAVATION	CU YD	75	75		60500060	REMOVING INLETS	EACH	2	2			
28100105	STONE RIPRAP, CLASS A3	SQ YD	29	29		60600605	CONCRETE CURB, TYPE B	FOOT	740	740			
28100203	STONE RIPRAP, CLASS A2	TON	27	27		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	271	271			
28100811	STONE DUMPED RIPRAP, CLASS A6	TON	570	570		61000225	TYPE F INLET BOX, STANDARD 610001	EACH	2	2			
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	1012	1012		60900515	CONCRETE THRUST BLOCKS	EACH	2	2			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	294	294		63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	925	925			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	59	59		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
44000100	PAVEMENT REMOVAL	SQ YD	250	250		63200310	GUARDRAIL REMOVAL	FOOT	1100	1100			
44003000	MEDIAN REMOVAL	FOOT	1227	1227		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	14			
44004250	PAVED SHOULDER REMOVAL	SQ YD	1073	1073		67100100	MOBILIZATION	L SUM	1	1			
45200300	JOINT OR CRACK FILLING	POUND	1629	1629		70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	2			
50102400	CONCRETE REMOVAL	CU YD	13.4	13.4		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
50300225	CONCRETE STRUCTURES	CU YD	64.7	64.7		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	143.5	143.5		70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1			
50300260	BRIDGE DECK GROOVING	SQ YD	4621	4621		70106700	TEMPORARY RUMBLE STRIP	EACH	12	12			
50300300	PROTECTIVE COAT	SQ YD	5555	5555		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	178	178			
50300530	FLOOR DRAIN EXTENSION	EACH	12	12		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3992	3992			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	31770	31770		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24			
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	35	35		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18	18			
50501130	STRUCTURAL STEEL REPAIR	POUND	400	400		70400100	TEMPORARY CONCRETE BARRIER	FOOT	1275	1275			
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1	1		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1275	1275			
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1		78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3992	3992			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	43600	43600		78100100	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4			
50800515	BAR SPLICERS	EACH	340	340		78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	90	90		78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14			
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	96	96		78200510	BARRIER WALL MARKERS, TYPE A	EACH	32	32			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	30	30		78300100	PAVEMENT MARKING REMOVAL	SQ FT	1331	1331			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10	10		X0321468	PLUG EXISTING DECK DRAINS	EACH	302	302			
52100520	ANCHOR BOLTS, 1"	EACH	140	140		X0322556	STIFFENER INTERSECTION MODIFICATION	EACH	104	104			
52100540	ANCHOR BOLTS, 1 1/2"	EACH	20	20		X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	400	400			
54215547	METAL END SECTIONS 12"	EACH	2	2		X8260110	NAVIGATION LIGHTING SYSTEM	L SUM	1	1			
58700300	CONCRETE SEALER	SQ FT	886	886									
60100945	PIPE DRAINS 12"	FOOT	69	69									

Rev.