

SUMMARY OF QUANTITIES

ST. CLAIR COUNTY

CODE NO.	ITEM	UNIT	URBAN		ROADWAY 100% STATE		CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	J000-2A				
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	1,047		1,047			
54213443	END SECTIONS 8"	EACH	2		2			
542C0213	PIPE CULVERTS, CLASS C, TYPE 1 8"	FOOT	14		14			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	54		54			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	643		643			
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	19		19			
55100200	STORM SEWER REMOVAL 6"	FOOT	1,340		1,340			
55100300	STORM SEWER REMOVAL 8"	FOOT	386		386			
55100400	STORM SEWER REMOVAL 10"	FOOT	409		409			
55100500	STORM SEWER REMOVAL 12"	FOOT	692		692			
55100700	STORM SEWER REMOVAL 15"	FOOT	647		647			
55100900	STORM SEWER REMOVAL 18"	FOOT	190		190			
55101200	STORM SEWER REMOVAL 24"	FOOT	95		95			
55101400	STORM SEWER REMOVAL 30"	FOOT	62		62			
60107700	PIPE UNDERDRAINS 6"	FOOT	140		140			
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	6		6			
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	10		10			
60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1			
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1		1			
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3		3			
60228120	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4		4			
60228130	MANHOLES, SANITARY, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5		5			
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	7		7			
60255500	MANHOLES TO BE ADJUSTED	EACH	4		4			
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9		9			
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1		1			
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	3		3			
60600605	CONCRETE CURB, TYPE B	FOOT	457		457			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	141		141			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,326		4,326			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75		75			
66400305	CHAIN LINK FENCE, 6'	FOOT	176		176			
66410300	CHAIN LINK FENCE REMOVAL	FOOT	2,290		2,290			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	90		90			
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1		1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1		1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8		8			
67100100	MOBILIZATION	L SUM	1		1			
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1			
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1		1			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156		156			

\* DENOTES SPECIALTY ITEMS

D:\BDCDNN-03\BORDER\JOB... \BDCDNN-03-S001.DGN, \BDCDNN-99-MOTIF.DGN, \BDCDNN-03-EGEND.DGN, 10-20-2009, 10:45:00

FILE NAME =	USER NAME = #USER#	DESIGNED - JB	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b> I-70 CONNECTION	<b>SUMMARY OF QUANTITIES 2</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - JB	CHECKED - ACL	REVISED -			9153	82-1K	ST. CLAIR	107	5
PLT SCALE = #SCALE#	DATE - 10/09/09	REVISED -				CONTRACT NO. 76C40				
PLT DATE = #DATE#						SCALE: N.T.S.	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	[ILLINOIS] FED. AID PROJECT



TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
CHICAGO, ILLINOIS

Rev