

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 TOTAL 4,326 FOOT					
FROM			TO		
LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
EXCHANGE ST.	49+30.36	16.13 RT	50+65.19	69.83 RT	167
EXCHANGE ST.	50+94.42	69.97 RT	57+99.13	48.45 RT	744
EXCHANGE ST.	58+25.27	49.13 RT	60+00	20.00 RT	189
EXCHANGE ST.	49+30.36	5.75 LT	60+00	20.00 LT	1,081
EXCHANGE ST.	60+00	20.00 RT	70+18.66	139.78 RT	1,101
EXCHANGE ST.	60+00	20.00 RT	70+17.65	76.08 LT	1,044

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS TOTAL 75 FOOT	
LOCATION	SUBTOTALS
MAIN ST. CUL DE SAC	75

CHAIN LINK FENCE, 6' TOTAL 176 FOOT						
LOCATION	FROM STA.	OFF.	TO STA.	OFF.	LENGTH (FT)	SUBTOTALS
EXCHANGE ST.	68+91.97	49.40 RT	69+95.04	61.57 RT	136	136
MAIN ST.	216+38.6	37.26 RT	216+74.73	20.08 RT	40	40

CHAIN LINK FENCE REMOVAL TOTAL 2,290 FOOT					
LOCATION	FROM STA.	OFF.	TO STA.	OFF.	SUBTOTALS
EXCHANGE	49+92.93	28.98 RT	50+60.23	23.98 RT	68
EXCHANGE	61+07.50	49.50 RT	61+72.69	122.63 LT	201
EXCHANGE	68+91.96	49.50 RT	69+95.04	61.57 RT	144
EXCHANGE	69+17.10	59.57 LT	69+16.41	34.65 RT	94
FRONT/MAIN ST.	216+41.05	39.00 RT	216+74.39	20.60 RT	55
FRONT/MAIN ST.	10+70.19	43.25 LT	215+69.88	222.0 RT	1,728

WORK ZONE PAVEMENT MARKING REMOVAL TOTAL 6,988 SQ FT				
TYPE OF MARKING	LENGTH (FT)	WIDTH (FT)	SUBTOTALS	
FROM TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	17,137	0.33	156	
FROM TEMPORARY PAVEMENT MARKING - LINE 4"	920	0.67	5,655	
FROM TEMPORARY PAVEMENT MARKING - LINE 8"	220	1	616	
FROM TEMPORARY PAVEMENT MARKING - LINE 12"	170	2	220	
FROM TEMPORARY PAVEMENT MARKING - LINE 24"			340	

TEMPORARY CONCRETE BARRIER TOTAL 1,025 FOOT	
LOCATION	SUBTOTALS
NE SIDE OF IL 3 FOR PROTECTION OF WORKERS	820
FOR PROTECTION OF HISTORIC RETAINING WALL	200

SIGN PANEL - TYPE 1 TOTAL 89 SQ FT						
LOCATION	STA.	OFF.	MUTCD ID	WIDTH (IN)	HEIGHT (IN)	SUBTOTALS
EXCHANGE ST.	51+19.2	38.2 RT	R1-1	30	30	6.25
EXCHANGE ST.	51+19.2	38.2 RT	R1-I100	30	18	3.75
EXCHANGE ST.	52+05.1	24.8 RT	R7-11	12	18	1.5
EXCHANGE ST.	52+68.9	25.0 RT	R2-1	24	30	5
EXCHANGE ST.	56+30.6	24.8 LT	R7-1R	12	18	1.5
EXCHANGE ST.	58+65.0	24.8 LT	CUSTOM	12	18	1.5
EXCHANGE ST.	57+41.5	24.8 RT	R7-11	12	18	1.5
EXCHANGE ST.	58+38.1	28.3 RT	R1-1	30	30	6.25
EXCHANGE ST.	58+38.1	28.3 RT	R1-I100	30	18	3.75
EXCHANGE ST.	60+35.6	24.8 RT	R7-11	12	18	1.5
EXCHANGE ST.	61+11.8	24.8 LT	R7-1L	12	18	1.5
EXCHANGE ST.	68+52.3	24.8 LT	R7-11	12	18	1.5
EXCHANGE ST.	69+12.4	25.0 LT	R2-1	24	30	5
EXCHANGE ST.	69+25.8	24.8 RT	R7-11	12	18	1.5
EXCHANGE ST.	69+84.5	39.9 RT	R1-1	30	30	6.25
EXCHANGE ST.	69+84.5	39.9 RT	R1-3	12	6	0.5
EXCHANGE ST.	70+66.8	20.9 LT	R1-1	30	30	6.25
EXCHANGE ST.	70+66.8	20.9 LT	R1-3	12	6	0.5
1ST ST.	5+78.04	55.1 LT	R1-1	36	36	9
1ST ST.	6+82.80	20.4 RT	R7-11	12	18	1.5
1ST ST.	20+08.1	25.2 RT	R1-1	30	30	6.25
1ST ST.	20+08.1	25.2 RT	R1-3	12	6	0.5
1ST ST.	20+96.7	40.8 LT	R1-1	30	30	6.25
1ST ST.	20+96.7	40.8 LT	R1-3	12	6	0.5
ST. CLAIR	85+24.4	71.13 RT	CUSTOM	18	24	3
MAIN ST.	223+00	26.0 LT	W14-2	30	30	6.25

REMOVE SIGN PANEL ASSEMBLY - TYPE A TOTAL 10 EACH				
LOCATION	STA.	OFF.	DESCRIPTION	SUBTOTALS
EXCHANGE	57+59.31	26.89' LT	STOP SIGN	1
EXCHANGE	58+33.28	11.45' LT	STOP SIGN	1
EXCHANGE	70+58.91	35.63' RT	STOP SIGN	1
EXCHANGE	70+65.93	19.71' LT	STOP SIGN	1
1ST STREET	6+01.55	19.96' RT	NO PARKING	1
1ST STREET	6+18.26	34.20' LT	STOP SIGN	1
FRONT ST.	200+45.10	28.77' LT	STOP SIGN	1
FRONT ST.	201+10.96	63.39' LT	STOP SIGN	1
FRONT ST.	200+71.34	28.83' LT	STREET SIGN	1
ST. CLAIR	85+87.91	69.54' RT	AUTO SHREDDER	1

REMOVE SIGN PANEL - TYPE 1 TOTAL 6 SQ FT							
LOCATION	STA.	OFF.	TYPE	WIDTH (IN)	HEIGHT (IN)	AREA (SF)	SUBTOTALS
1ST STREET	21+17.39	53.29' LT	STOP SIGN	30	30	6.25	6.25

METAL POST - TYPE A TOTAL 251 FOOT				
LOCATION	STA.	OFF.	ESTIMATED LENGTH (FT)	SUBTOTALS
EXCHANGE ST.	51+19.2	38.2 RT	14.5	14.5
EXCHANGE ST.	52+05.1	24.8 RT	12.5	12.5
EXCHANGE ST.	52+68.9	25.0 RT	13	13
EXCHANGE ST.	56+30.6	24.8 LT	12.5	12.5
EXCHANGE ST.	57+41.5	24.8 RT	12.5	12.5
EXCHANGE ST.	58+38.1	28.3 RT	14.5	14.5
EXCHANGE ST.	60+35.6	24.8 RT	12.5	12.5
EXCHANGE ST.	61+11.8	24.8 LT	12.5	12.5
EXCHANGE ST.	68+52.3	24.8 LT	12.5	12.5
EXCHANGE ST.	69+12.4	25.0 LT	13	13
EXCHANGE ST.	69+25.8	24.8 RT	12.5	12.5
EXCHANGE ST.	69+84.5	39.9 RT	13.5	13.5
EXCHANGE ST.	70+66.8	20.9 LT	13.5	13.5
1ST ST.	5+78.0	55.1 LT	13.5	13.5
1ST ST.	6+82.8	20.4 RT	13.5	13.5
1ST ST.	20+08.1	25.2 RT	13.5	13.5
1ST ST.	20+96.7	40.8 LT	13.5	13.5
MAIN ST.	223+00	26.0 LT	13.5	13.5
ST. CLAIR	85+24.4	71.13 RT	13.5	13.5

COMBINED SEWER REMOVAL 30" TOTAL 519 FOOT				
STA.	OFF.	STA.	OFF.	SUBTOTALS
64+41.69	34.62 RT	67+01.82	50.17 RT	260
67+01.82	50.17 RT	68+36.41	51.8 RT	134
68+36.41	51.8 RT	69+62.11	51.83 RT	125

AGGREGATE SURFACE COURSE, TYPE B 8" TOTAL 138 SQ YD				
LOCATION	FROM STA.	TO STA.	AREA (SF)	SUBTOTALS
EXCHANGE	68+95.4 RT	69+73.7 RT	1241.04	137.89

COMBINED SEWERS TO BE CLEANED TOTAL 1,529 FOOT					
LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS
EXCHANGE	48+51.60	-9.66	50+69.60	-5.77	218
EXCHANGE	50+72.25	-5.72	51+92.09	-3.06	118
EXCHANGE	51+95.40	-3.18	53+14.88	-5.00	118
EXCHANGE	53+18.21	-4.94	54+24.99	-4.96	105
EXCHANGE	54+27.86	-4.85	55+11.65	-17.39	86
EXCHANGE	55+14.42	-18.14	55+71.06	-35.48	56
EXCHANGE	55+74.22	-36.2	56+24.57	-45.96	44
EXCHANGE	56+28.39	-46.36	57+40.86	-49.14	106
EXCHANGE	57+44.14	-49.13	60+06.04	-49.33	262
EXCHANGE	60+09.29	-49.36	62+26.50	-11.35	208
EXCHANGE	62+29.44	-10.03	64+40.20	34.38	208

UTILITY STRUCTURE REMOVAL TOTAL 9 EACH				
DESCRIPTION	STA.	OFF.	LT/RT	SUBTOTALS
ELECT/TELE	52+88.0	27.37	RT	1
WATER	54+18.0	6.51	RT	1
WATER	54+90.3	23.05	LT	1
WATER	54+98.0	23.88	LT	1
WATER	55+88.0	16.89	LT	1
WATER	57+65.6	24.65	LT	1
WATER/W.U.	57+69.7	18.37	LT	1
WATER/W.U.	58+57.2	21.83	LT	1
WATER	59+83.2	24.63	LT	1

AGGREGATE SUBGRADE 12" TOTAL 9,606 SQ YD	
ITEM	SUBTOTALS
ITEM 42000541 PCC PAVEMENT 12" (JOINTED)	7,744
AREA OUTSIDE PCC PAVEMENT = CURB & GUTTER LENGTH (B-6.24) X CURB & GUTTER WIDTH + 6"/9	1,480
OMIT SUBGRADE UNDER CC&G (B-6.24) 49+30.36 TO 55+41.84	-428
AREA OUTSIDE PCC PAVEMENT = CURB & GUTTER LENGTH (B-6.12)	33
MAIN ST. CUL DE SAC	224
ITEM 35300500 PCC BSE CSE 10"	553

CONCRETE REMOVAL (SPECIAL) TOTAL 1,231 SQ YD					
FROM STA.	TO STA.	OFF.	AREA (SF)	SUBTOTALS	
53+18.42	49.50	55+68.61	-10.36	10,933	1,215
69+46.69	2.05	69+45.19	-57.15	143	16

DOWEL BARS 1 1/2" TOTAL 1,370 EACH	
ITEM	SUBTOTALS
80 PATCHES @ 9 FT X 2 SIDES PER PATCH X 8 DOWELS PER SIDE =	1,280
3 PATCHES @ 6 FT X 2 SIDES PER PATCH X 5 DOWELS PER SIDE =	90

DRAINAGE STRUCTURE TO BE REMOVED TOTAL 47 EACH				
LOCATION	FROM STA.	OFF.	LT/RT	SUBTOTALS
EXCHANGE AVE	51+42.4	45.52	RT	1
EXCHANGE AVE	51+92.1	9.68	LT	1
EXCHANGE AVE	53+16.5	1,945	RT	1
EXCHANGE AVE	53+38.7	30.48	RT	1
EXCHANGE AVE	53+72.6	30.37	RT	1
EXCHANGE AVE	54+03.9	27.74	RT	1
EXCHANGE AVE	54+05.1	31.57	RT	1
EXCHANGE AVE	54+24.0	2.77	RT	1
EXCHANGE AVE	54+34.9	2.98	RT	1
EXCHANGE AVE	54+37.4	21.93	RT	1
EXCHANGE AVE	54+68.1	45.97	RT	1
EXCHANGE AVE	54+70.7	22.92	RT	1
EXCHANGE AVE	54+94.2	18.87	RT	1
EXCHANGE AVE	55+02.3	40.15	RT	1
EXCHANGE AVE	55+26.9	10.71	RT	1
EXCHANGE AVE	55+35.6	31.97	RT	1
EXCHANGE AVE	55+81.6	31.22	LT	1
EXCHANGE AVE	56+15.2	30.87	RT	1
EXCHANGE AVE	56+49.8	39.45	LT	1
EXCHANGE AVE	56+52.9	1.53	RT	1
EXCHANGE AVE	57+06.0	14.57	RT	1
EXCHANGE AVE	57+12.8	39.23	LT	1
EXCHANGE AVE	57+88.1	26.36	LT	1
EXCHANGE AVE	58+24.9	8.63	LT	1
EXCHANGE AVE	59+77.9	39.89	LT	1
EXCHANGE AVE	59+92.7	34.55	LT	1
EXCHANGE AVE	62+25.8	0.71	RT	1
EXCHANGE AVE	67+01.1	50.17	RT	1
EXCHANGE AVE	67+80.8	43.22	RT	1
EXCHANGE AVE	68+36.7	52.01	RT	1
EXCHANGE AVE	69+62.7	40.90	RT	1
EXCHANGE AVE	69+62.3	51.58	RT	1
FRONT / MAIN ST.	213+56.1	193.29	LT	1
FRONT / MAIN ST.	213+53.9	127.49	LT	1
FRONT / MAIN ST.	213+50.0	63.85	LT	1
FRONT / MAIN ST.	213+42.9	75.30	LT	1
FRONT / MAIN ST.	212+83.7	24.54	RT	1
FRONT / MAIN ST.	210+62.6	13.10	RT	1
FRONT / MAIN ST.	210+57.6	61.19	RT	1
FRONT / MAIN ST.	207+20.2	78.70	LT	1
FRONT / MAIN ST.	207+15.4	77.92	LT	1
FRONT / MAIN ST.	207+15.8	86.01	LT	1
FRONT / MAIN ST.	206+38.6	11.76	RT	1
FRONT / MAIN ST.	206+26.2	60.69	RT	1
FRONT / MAIN ST.	205+87.2	62.78	RT	1
FRONT / MAIN ST.	204+25.9	46.93	LT	1
FRONT / MAIN ST.	202+81.7	33.79	RT	1

FENCE REMOVAL TOTAL 1,724 FOOT				
--------------------------------	--	--	--	--