GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
- 2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING, FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

*COMMUNICATIONS: AT&T CORPORATION

866 ROCK CREEK ROAD PLANO, IL 60545-9571

*WATER: FOUNTAIN WATER DISTRICT

732 QUARRY ROAD VALMEYER, IL 62295

*COMMUNICATIONS: HARRISONVILLE TELEPHONE CO.

213 S. MAIN STREET

PO BOX 149

WATERLOO, IL 62298-0149

*ELECTRIC:

MONROE COUNTY ELECTRIC CO-OPERATIVE, INC. 6132 STATE ROUTE 3

PO BOX 128

WATERLOO, IL 62298

*COMMUNICATIONS: VERIZON NORTH, INC.

SOUTHERN DIVISION 111 E. STATE STREET MASCOUTAH. IL 62258

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY . NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)

3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

4. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE USE AC/PG

SHOULDERS PG 58-22

*SHOULDER-TOP LIFT PG 58-22

RAP % (MAX) 30% 2.0% @ Ndes=30 2.0% @ Ndes=30

DESIGN AIR VOIDS

MIX COMPOSITION (GRADATION MIXTURE)

FRICTION AGG.

- DESIGN THIS MIX AT 2.0% AIR VOIDS AND ADD ASPHALT TO REDUCE AIR VOIDS TO 1.5%.
- 5. FLAGGERS SHALL BE PRESENT DURING ALL CLOSURE HOURS INCLUDING LUNCH HOUR AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
- 6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT PLUS THE INTERSECTING SIDEROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE 48" X 48" FLUORESCENT ORANGE.
- 7. ALL TRAFFIC CONTROL DEVICES AS HEREIN SPECIFIED AND ANY ADDITIONAL TRAFFIC CONTROL DEVICES AND FLAGGERS AS DEEMED NECESSARY BY THE RESIDENT ENGINEER SHALL BE INCLUDED IN THE COST OF THE CONTRACT TRAFFIC CONTROL PAY ITEMS.
- 8. A QUANTITY FOR EARTH EXCAVATION IS PROVIDED FOR EARTHWORK REQUIRED FOR THE CONSTRUCTION OF HOT-MIX ASPHALT SHOULDERS. TRENCHES SHALL BE FILLED THE SAME DAY.
- 9. CARE SHALL BE TAKEN NOT TO DAMAGE THE EXISTING CULVERTS UNDER THE ROADWAY. ANY NECESSARY REPAIRS DUE TO DAMAGE INCURRED DURING THESE OPERATIONS AND ANY ADJUSTMENTS TO SHOULDER DEPTH AS DEEMED NECESSARY BY THE RESIDENT ENGINEER SHALL BE INCLUDED IN THE COSTS OF EARTH EXCAVATION AND HOT-MIX ASPHALT SHOULDERS. 8".
- 10. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.

USER NAME = \$USER\$

PLOT SCALE = #SCALE#

PLOT DATE = \$DATE\$

ILE NAME :

SFILEL\$

- 11. CARE SHALL BE TAKEN NOT TO DAMAGE THE EXISTING EDGELINE PAVEMENT MARKING ON IL 3. ANY DAMAGE TO PAVEMENT MARKING DUE TO THESE OPERATIONS SHALL BE REPAIRED AT CONTRACTOR EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER.
- 12. ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND APPROPRIATE LIGHTS.

11 3

4	11. 0				
	SCHEDULE				
LOCATION		THERMOPLASTIÇ PVMT MRK - LINE 4"			
		SKIP DASH 10'/30'	SOLID	RUMBLE STRIPS	
	LENGTH	YELLOW	YELLOW		
	FOOT	FOOT	FOOT	FOOT	
STA. 301+50.34 TO STA. 306+50 - NPZ SB	500	125	500	500	
STA. 306+50 TO STA. 308+65 - NPZ NB&SB	215		430	215	
STA. 308+65 TO STA. 309+79.45 - NPZ NB	115	29	115	115	
STA. 309+79.45 TO STA. 326+69.24 - OMISSION	1690				
STA. 326+69.24 TO STA. 329+75 - NPZ SB	306	77	306	306	
STA. 329+75 TO STA. 351+39.63 - NPZ NB&SB	2165		4330	2165	
,					
SUBTOTAL		231	5681	3301	
TOTAL		5912		3301	

II 156

		SCHEDULE				
LOCATION	LENGTH	EARTH EXCAVATION	HMA SHOULDERS, 8"	SHOULDER RUMBLE STRIP	AGGREGATE WEDGE SHOULDER, TYPE B	THERMOPLASTIC PVMT MRK - LINE 4 SOLID WHITE
	FOOT	CU YD	SO YD	- F00T	TON	FOOT
STA. 266+20 TO STA. 286+47 RT	2027	150	676	2027	51	2027
STA. 286+77 TO STA. 348+50 RT	6173	457	2058	6173	156	6173
STA. 266+20 TO STA. 312+98 LT	4678	346	1559	4678	118	4678
STA. 313+18 TO STA. 348+50 LT	3532	261	1177 .	3532	89	3532
	·				***************************************	
			,			
TOTAL	*	1214	5470	16410	414	16410

• 829 & 14

DESIGNED -REVISED -COUNTY TOTAL SHEETS NO. Allen Henderson & Associates, Inc. SECTION **GENERAL NOTES & SCHEDULES** REVISED -DRAWN -Civil and Structural Engineers Springfield, IL. MONROE 6 DIST 8 SHOULDER 2010-1 CHECKED -REVISED -62703 Phone: (217)544-8033 IL. Design Firm CONTRACT NO. 76D38 No. 184-001907 SCALE: NONE SHEET NO. 2 OF 6 SHEETS STA. DATE REVISED FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT