

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 LOCATION 1 <i>FAU 9166</i>	1000 LOCATION 2 <i>FAU 9331</i>	Y031-IF LOCATION 1 <i>FAU 9166</i>	Y031-IF LOCATION 2 <i>FAU 9331</i>
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	261.8	261.8			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	865.8	339.3	526.5		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1376.8	1307.2	69.6		
50105220	PIPE CULVERT REMOVAL	FOOT	16		16		
50800105	REINFORCEMENT BARS	POUND	61.5	61.5			
54002060	EXPANSION BOLTS 3/4 INCH X 12 INCH	EACH	12	12			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	3	3			
54213870	STEEL END SECTIONS 15"	EACH	1		1		
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	3	3			
54248510	CONCRETE COLLAR	CU YD	1	1			
542A0235	PIPE CULVERTS, CLASS A, TYPE I 30"	FOOT	21	21			
542D0220	PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	18		18		
550A4300	STORM SEWERS, CLASS A, TYPE I EQUIVALENT ROUND-SIZE 30"	FOOT	85	85			
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	11	11			
60260600	INLETS TO BE ADJUSTED WITH NEW TYPE 4 FRAME AND GRATE	EACH	1	1			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4			
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	2	2			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	122	122			
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	48	48			
60621200	CONCRETE MEDIAN, TYPE SB-9.24	SO FT	106.6	106.6			
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	300	300			
*63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	306.25	306.25			
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	43.75	43.75			
*63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	2			
*63100169	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) FLARED	EACH	5	5			
63200310	GUARDRAIL REMOVAL	FOOT	1531.3	1531.3			
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	450	450			
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE I	EACH	1	1			

** Specialty Items*

FILE NAME *	USER NAME * alfordb	DESIGNED -	REVISED -
ca:\pe_work\spidot\alfordb\08174224\0876	99-shc-plan.dgn	DRAWN - TRF	REVISED -
PLOT SCALE * 1/8" = 1'		CHECKED -	REVISED -
PLOT DATE * 3/2/2010		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0331/9966	32RS-3, 31RS-3, 1RS-1	ST. CLAIR	56	4
CONTRACT NO. 76069			ILLINOIS FED. AID PROJECT	