

HMA RESURFACING							
LOCATION			SURFACE REMOVAL	BITUMINOUS MATERIALS (PRIME)	LEVELING BINDER 3/4"	HMA SURFACE 1 1/2"	AGG. SHLDRS TYPE B (1')
STA.	TO	STA.	(SQ YD)	(TON)	(TON)	(TON)	(TON)
1+00	TO	94+38		35.7	958.7	1917.4	247.9
BUTT JOINT	@	1+00 (BEGIN JOB)	146.7	0.25		15.6	
BUTT JOINT	@	PARK ROAD (82+29 RT)	99.4	0.20		10.6	
ENTRANCES	&	SIDE ROADS		0.31		12.4	
BUTT JOINT	@	94+38 (END JOB)	300.0	0.45		31.9	
SURFACE	&	SLOPE IMPERFECTIONS			370.7		
TOTALS:			546.1	37	1329	1988	247.9

THERMOPLASTIC PAVEMENT MARKING -LINE 4"					
LINE 4 INCH					
LOCATION			DOUBLE YELLOW	SOLID YELLOW (NPZ)	YELLOW SKIP DASH
STA	TO	STA	(FOOT)	(FOOT)	(FOOT)
FORT KASKASKIA RD					
1+00	TO	11+45			261.3
11+45	TO	18+05		660 (RT)	165
18+05	TO	23+53	1096		
23+53	TO	32+81		928 (LT)	232
32+81	TO	34+58	354		
34+58	TO	44+23		965 (RT)	241.2
44+23	TO	94+38	10030		
SUB-TOTAL			11480	2553	899.5
TOTAL:					14932.5

TEMPORARY RAMPS	
LOCATION/DESCRIPTION	TEMPORARY RAMPS (SQ YD)
STA 1+00 (BEGIN JOB)	12.2
PARK ROAD STA 82+29 (RT)	41.1
STA 94+38 (END JOB)	37.8
TOTAL:	91.1

FILE NAME *	USER NAME * e1fordb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	OR	SECTION	COUNTY	TOTAL	SHEET	
ca\pe...ork\PI\DOT\VAL\FOR08\08174288\0876\072-shr-plan.dgn		DRAWN -	REVISED -			059	90-1-RS	RANDOLPH	8	6	
PLOT SCALE * 1/8"=1'-0"		CHECKED -	REVISED -			CONTRACT NO. 76072					
PLOT DATE * 1/28/2018		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.