

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000-2A ST. CLAIR	1000-2A CLINTON	CODE NO	ITEM	UNIT		1000-2A ST. CLAIR	1000-2A CLINTON
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	140	140		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	400		400
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	4644		4644	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	298		298
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	498		498	70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	19	19	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	61.7	13.7	48	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2488	545	1943
40600300	AGGREGATE (PRIME COAT)	TON	295.6	65.5	230.1	*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	665.6		665.6
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	8331	1835	6496	*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	178182	38454	139728
40600990	TEMPORARY RAMP	SQ YD	455	27	428	*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	400		400
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	16774	3680	13094	*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	298		298
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	4644		4644	*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	19	19	
44000100	PAVEMENT REMOVAL	SQ YD	4644		4644	*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1027	205	822
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	184383	43680	140703	*78200410	GUARDRAIL MARKERS, TYPE A	EACH	12		12
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9114		9114	*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1		1
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5160		5160	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1010	191	819
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2266	560	1706	*80300100	LOCATING UNDERGROUND CABLE	FOOT	125		125
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	912.5		912.5	*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1886		1886
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1		1						
63200310	GUARDRAIL REMOVAL	FOOT	987.5		987.5						
*63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	25		25						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10		10						
67100100	MOBILIZATION	L SUM	1		1						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1						
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1						
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60		60						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29874	6552	23322						
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	655.6		655.6						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	178182	38454	139728						

** Specialty Items*