

# SCHEDULES

PAVEMENT MARKING SCHEDULE												
LOCATION		THERMOPLASTIC PAVEMENT MARKING									LETTERS AND SYMBOLS	
		LINE - 4"			LINE - 8"		LINE - 12"		LINE - 24"			LETTERS AND SYMBOLS
		WHITE			YELLOW		WHITE		WHITE			
		SOLID	SKIP DASH	SKIP DASH	SOLID	SKIP DASH	SOLID	SOLID	SOLID	SKIP DASH		
STA TO	STA	(FT)	10'-30'-10' (FT)	2'-6'-2' (FT)	10'-30'-10' (FT)	(FT)	(FT)	(FT)	10'-30'-10' (FT)	(SQ FT)		
<b>LOCATION # 1</b>												
10+30	TO 11+60	(NO PASS ZN EB/WB)			260				19			
11+60	TO	18+43	1366		1366							
18+43	TO	26+00	1514		757	190						
26+00	TO	173+80	29560			3695						
OMISSION AT		SUMMERFIELD RD(NORTH)	-114									
OMISSION AT		SUMMERFIELD RD(SOUTH)	-75									
OMISSION AT		TOLER RD	-65									
SUBTOTAL 1			32186	0	0	2383	3885		19	0		

THERMOPLASTIC PAVEMENT MARKING												
LOCATION		THERMOPLASTIC PAVEMENT MARKING									LETTERS AND SYMBOLS	
		LINE - 4"			LINE - 8"		LINE - 12"		LINE - 24"			LETTERS AND SYMBOLS
		WHITE			YELLOW		WHITE		WHITE			
		SOLID	SKIP DASH	SKIP DASH	SOLID	SKIP DASH	SOLID	SOLID	SOLID	SKIP DASH		
STA TO	STA	(FT)	10'-30'-10' (FT)	2'-6'-2' (FT)	10'-30'-10' (FT)	(FT)	(FT)	(FT)	10'-30'-10' (FT)	(SQ FT)		
<b>LOCATION # 2</b>												
32+92	TO	54+20	3956			532						
85+05	TO	120+58	1768		6672	1150	400	298		665.6		
120+58	TO	414+96				7360						
240+56	TO	246+56			600							
250+32	TO	257+12			680							
267+20	TO	275+60			840							
279+20	TO	288+80			960							
361+84	TO	372+64			1080							
372+64	TO	383+84			1120							
403+36	TO	414+96			1160							
414+96	TO	420+16			1040							
420+16	TO	431+36			1120							
420+16	TO	444+56				610						
435+76	TO	444+56			880							
444+56	TO	478+88			6864							
120+58	TO	478+88	69460									
SUBTOTAL 2			75184		23016	9652						

LOCATION		THERMOPLASTIC PAVEMENT MARKING										LETTERS AND SYMBOLS
		LINE - 4"			LINE - 8"		LINE - 12"		LINE - 24"		LETTERS AND SYMBOLS	
		WHITE			YELLOW		WHITE		WHITE			
		SOLID	SKIP DASH	SKIP DASH	SOLID	SKIP DASH	SOLID	SOLID	SOLID	SKIP DASH		
STA TO	STA	(FT)	10'-30'-10' (FT)	2'-6'-2' (FT)	10'-30'-10' (FT)	(FT)	(FT)	(FT)	10'-30'-10' (FT)	(SQ FT)		
<b>LOCATION #3</b>												
10+00	TO	68+32	11664					1458				
68+32	TO	73+52	1040			520	130					
73+52	TO	80+77	1450				181					
80+77	TO	85+97	1040			520	130					
85+97	TO	94+37	1680				210					
94+37	TO	99+97	1120			560	140					
99+97	TO	105+57	1120				140					
105+57	TO	109+97	880			440	110					
109+97	TO	145+97	7200				900					
OMISSION AT		BARTELSD RD	-160									
OMISSION AT		BECKMEYER RD	-90									
OMISSION AT		RANDALL ST	-53									
OMISSION AT		McKINLEY ST	-53									
OMISSION AT		LOUIS ST	-63									
OMISSION AT		ELIZABETH ST	-58									
OMISSION AT		HARPER ST	-80									
OMISSION AT		PIPELINE RD (SOUTH)	-100									
OMISSION AT		PIPELINE RD (NORTH)	-100									
SUBTOTAL 3			26437	0	0	2040	3399			0	0	
TOTAL			1E+05			27439	16936	400	298	19	665.6	

### GUARDRAIL SCHEDULE

LOCATION		GUARD RAIL REMOVAL	SPBGR TYPE A	TBT TY 1 (SPECIAL) TANGENT	GUARDRAIL MARKER TYPE A	TERMINAL MARKER DIRECT APPLIED	SPBGR SHORT RADIUS
STA TO	STA	(FT)	(FT)	(EACH)	(EACH)	(EACH)	(FT)
<b>LOCATION #2</b>							
124+40	TO	134+27	LT	987.5	912.5	1	12
TOTAL				987.5	912.5	1	12