

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONST. TYPE CODE J000-1A	
		UNIT	TOTAL QUANTITIES 80% FED 20% STATE
X0325807	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2"	SO YD	12598
X0556100	PARTIAL DEPTH PATCHING (SPECIAL)	SO YD	569
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017100	DOWEL BARS	EACH	1040
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	190
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	143
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	143
20200100	EARTH EXCAVATION	CU YD	2775
* 20200200	ROCK EXCAVATION	CU YD	446
25000115	SEEDING, CLASS 1B	ACRE	1.18
25000350	SEEDING, CLASS 7	ACRE	1.18
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.37
25100115	MULCH, METHOD 2	ACRE	2.37
25100630	EROSION CONTROL BLANKET	SO YD	5750
28000305	TEMPORARY DITCH CHECKS	FOOT	84
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	238
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SO YD	2011
35501334	HOT-MIX ASPHALT BASE COURSE, 12 1/2"	SO YD	2031
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1201
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3
40600300	AGGREGATE (PRIME COAT)	TON	21
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	234
40600990	TEMPORARY RAMP	SO YD	154
40603525	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	1024
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1251
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	80
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	1908
44000400	GUTTER REMOVAL	FOOT	4824
42001200	PAVEMENT FABRIC	SO YD	79
42001300	PROTECTIVE COAT	SO YD	1966
44213200	SAW CUTS	FOOT	2222
44000100	PAVEMENT REMOVAL	SO YD	1163
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	388
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	79
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1864
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	5951
60500060	REMOVING INLETS	EACH	6
60602800	CONCRETE GUTTER, TYPE B	FOOT	206
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1

* Specialty Items

FILE NAME =
c:\pwwork\pwwork\naasdp\d8113864\78113-
ht*misc.dgn

USER NAME = naasdp
PLOT SCALE = 45,0000' / 1" IN.
PLOT DATE = 1/28/2010

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
148/37	113(N-1)	WILLIAMSON	91	3
CONTRACT NO. 78113				
ILLINOIS FED. AID PROJECT				