

### EARTHWORK SCHEDULE

LOCATION STATION TO STATION	ROCK EXCAVATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)
<b>IL 148/37</b>					
Sta. 27+08 to 63+53	245	2111	1583	1367	216
<b>IL 37</b>					
Sta. 0+24.06 to 13+50	139	582	437	64	373
<b>NE QUADRANT</b>					
0+00 to 1+63.70	56	29	22	111	-89
<b>SE QUADRANT</b>					
0+00 to 1+64.07	6	53	40	82	-42
<b>TOTALS</b>	446	2775	2081	1624	457

25% SHRINKAGE FOR EARTH EXCAVATION  
ROCK EXCAVATION SHOULD BE WASTED, NOT USED IN PROPOSED EMBANKMENT

### DETOUR SIGNING

SIGN ID NO.	DESCRIPTION	SIGN SIZE	SIGN AREA (SQ FT)	NUMBER REQUIRED EACH WAY		TOTAL SIGNS REQUIRED	SIGN PANEL TYPE 1 (0-9) (SQ FT)	SIGN PANEL TYPE 2 (9-24) (SQ FT)
				NORTH/SOUTH				
M6-1	→	21" X 15"	2.188	NORTH	1	3	6.56	
				SOUTH	2			
M6-2R	↗	21" X 15"	2.188	NORTH	2	5	10.94	
				SOUTH	3			
M5-1R	↘	21" X 15"	2.188	NORTH	0	1	2.19	
				SOUTH	1			
M6-3	↑	21" X 15"	2.188	NORTH	2	3	6.56	
				SOUTH	1			
M1-4	IL ROUTE 37	24" X 24"	4.000	NORTH	6	13	52.00	
				SOUTH	7			
R3-2L	⊗	24" X 24"	4.000	NORTH	0	1	4.00	
				SOUTH	1			
R3-1R	⊗	24" X 24"	4.000	NORTH	1	1	4.00	
				SOUTH	0			
W20-2	DETOUR AHEAD	48" X 48"	16.000	NORTH	1	2		32.00
				SOUTH	1			
M4-8	DETOUR	12" X 24"	2.000	NORTH	6	13	26.00	
				SOUTH	7			
W20-3	ROAD CLOSED AHEAD	48" X 48"	16.000	NORTH	1	2		32.00
				SOUTH	1			
R11-3A	ROAD CLOSED 9 MILES AHEAD LOCAL TRAFFIC ONLY	60" X 30"	12.500	NORTH	0	1		12.50
				SOUTH	1			
<b>TOTALS</b>							112.256	76.5

### SEEDING AND EROSION CONTROL

LOCATION STATION TO STATION	SEEDING CLASS 1B	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE	EROSION CONTROL BLANKET	SEEDING CLASS 7	TEMPORARY DITCH CHECKS
	( ACRE )	( POUND )	( POUND )	( POUND )	( ACRE )	( TON )	( SQ YD )	( ACRE )	( EACH )
<b>IL 148/37</b>									
44+00 TO 63+00	0.847	135.52	101.64	101.64	1.694	1.694	4099.48	0.847	
47+50 LT.									1
49+50 LT.									1
53+50 LT.									1
55+50 LT.									1
57+50 LT.									1
<b>IL 37</b>									
0+24 TO 12+95	0.341	54.56	40.92	40.92	0.682	0.682	1650.44	0.341	
3+00 LT.									1
10+75 LT.									1
<b>TOTALS</b>	1.188	190.08	142.56	142.56	2.376	2.376	5749.92	1.188	7