

SUMMARY OF QUANTITIES

FAP 332 (IL14/1)

CODE NUMBER	ITEM	CONSTRUCTION TYPE CODE	TOTAL QUANTITIES
		ITEM	Y031-IF TRAFFIC SIGNALS 100% STATE
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	915
42400800	DETECTABLE WARNINGS	SQ FT	64
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	66
44000600	SIDEWALK REMOVAL	SQ FT	915
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	66
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3
80300100	LOCATING UNDERGROUND CABLE	FOOT	200
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	6
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	35
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	33
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	4
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	77
81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT	51
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	78
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	392
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	794
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	424
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	286
87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2
87900100	DRILL EXISTING FOUNDATION	EACH	3
87900200	DRILL EXISTING HANDHOLE	EACH	12
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4
88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	4
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	4
88600100	DETECTOR LOOP, TYPE I	FOOT	272
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1