

SUMMARY OF QUANTITIES) 100% STATE

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FRANKLIN CO.	WILLIAMSON CO.
				ROADWAY RURAL	ROADWAY RURAL
CONSTRUCTION TYPE CODE				1000	1000
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SO YD	331,380	236,399	94,981
X0301424	SILICONE JOINT SEALER	FOOT	176	176	
X0322278	RODENT SHIELDS	EACH	360	228	132
X0322729	MATERIAL TRANSFER DEVICE	TON	209,027	152,716	56,311
X0325570	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	82	59	23
X0325571	TRAFFIC CONTROL SUPERVISOR	CAL DA	82	59	23
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.7	0.3
X0325747	BRIDGE DECK CONCRETE CRACK SEALER	FOOT	2,286	2,286	
X0326223	FOAM, EXPANDING POLYURETHANE, HIGH-DENSITY	POUND	5,760	5,760	
Z0017202	DOWEL BARS 1 1/2"	EACH	3,198	2,818	380
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	19	19	
Z0075310	TIE BARS 3/4"	EACH	12	12	
Z0076600	TRAINEES	HOURL	2,000	1,000	1,000
20200100	EARTH EXCAVATION	CU YD	95	95	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	5,671	4,200	1,471
25000200	SEEDING, CLASS 2	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2	0.2	
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SO YD	524	524	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	58,356	42,141	16,215
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35,633	26,221	9,412
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	7	3
40600982	HOT-MIX SURFACE REMOVAL - BUTT JOINT	SO YD	2,615	1,544	1,071
40600990	TEMPORARY RAMP	SO YD	507	327	180
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	114,970	83,280	31,690
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	50,478	37,361	13,117
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	43,579	32,075	11,504
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	386	147	239
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	25,541	21,017	4,524
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	7,192	6,992	200
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	220,179	220,179	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	159,210	56,883	102,327
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	1,404	1,100	304

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\colemm\8171161\78175-h-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	98	13
PLOT SCALE = 100.0000 "/ IN.		CHECKED -	REVISED -						CONTRACT NO. 78175				
PLOT DATE = 1/28/2010		DATE -	REVISED -						FRANKLIN, WILLIAMSON				