

## GUARDRAIL SCHEDULE FRANKLIN CO.

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBCR TYPE A FOOT	TRAFFIC BARRIER TERMINAL					GUARDRAIL MARKERS EACH	VERTICAL ADJUSTMENT FOOT	TERMINAL MARKERS DIRECT APPLIED EACH	CONCRETE CURB, TYPE B FOOT	COMMENTS
			TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 5 EACH	TYPE 6 EACH	TYPE 6B EACH					
<b>NORTHBOUND</b>												
490+60.00 TO 493+17.00	257.00						1				SE QUAD OF 028-0022	
490+49.40 TO 491+05.65		226.25						3			SE QUAD OF 028-0022	
491+05.65 TO 493+31.90			1					1		1	SE QUAD OF 028-0022	
493+31.90 TO 493+81.90											SE QUAD OF 028-0022	
499+10.00 TO 502+51.00	341.00											
499+07.00 TO 503+44.50		437.50		1				6			SE AND NE QUAD OF 028-0063 ON EAST SIDE OF EXIT RAMP	
503+44.50 TO 503+94.50			1					1		1		
479+97.00 TO 482+75.00	278.00										SE QUAD OF 028-0010	
479+84.00 TO 480+40.25							1	1			SE QUAD OF 028-0010	
480+40.25 TO 482+66.50		226.25						3			SE QUAD OF 028-0010	
482+66.50 TO 483+16.50			1					1		1	SE QUAD OF 028-0010	
479+57.00 TO 479+87.00	30.00										NE QUAD OF 028-0010	
479+47.33 TO 479+72.33		25.00		1				1			NE QUAD OF 028-0010	
479+72.33 TO 479+87.00					1			1			NE QUAD OF 028-0010	
511+05.00 TO 512+30.00								2	125.00		NE QUAD OF 028-0009	
498+43.00 TO 511+05.00		1262.00		1				16				
515+61.00 TO 518+80.00								4	319.00		SE QUAD OF 028-0009	
518+80.00 TO 527+54.00	874.00											
518+80.00 TO 527+05.00		825.00						11				
527+05.00 TO 527+55.00			1					1		1		
576+58.00 TO 579+06.60	248.60										SE QUAD OF 028-0054	
576+58.00 TO 577+14.25							1	1			SE QUAD OF 028-0054	
577+14.25 TO 579+40.50		226.25						3			SE QUAD OF 028-0054	
579+40.50 TO 579+90.50			1					1		1	SE QUAD OF 028-0054	
629+92.00 TO 632+35.50	243.50										SE QUAD OF 028-0062	
629+80.40 TO 630+36.65								1			SE QUAD OF 028-0062	
630+36.65 TO 632+62.90		226.25						3			SE QUAD OF 028-0062	
632+62.90 TO 633+12.90			1					1		1	SE QUAD OF 028-0062	
651+00.00 TO 654+00.00		300.00		1				4				
654+00.00 TO 654+50.00			1					1		1		
35+83.00 TO 42+56.00	673.00										NE QUAD OF 028-0006	
35+78.50 TO 36+28.50				1				1			NE QUAD OF 028-0006	
36+28.50 TO 42+09.75		581.25						8			NE QUAD OF 028-0006	
42+09.75 TO 42+56.00							1	1		38.8	NE QUAD OF 028-0006	
46+42.00 TO 49+67.00	325.00										SW QUAD OF 028-0006	
46+42.00 TO 46+88.25								1		38.8	SW QUAD OF 028-0006	
46+88.25 TO 50+19.50		331.25						5			SW QUAD OF 028-0006	
50+19.50 TO 50+69.50			1					1		1	SW QUAD OF 028-0006	
46+42.00 TO 81+35.00	3493.00										SE QUAD OF 028-0006	
46+42.00 TO 46+88.25								1		38.8	SE QUAD OF 028-0006	
46+88.25 TO 81+35.00		3446.75						44			SE QUAD OF 028-0006	
81+35.00 TO 116+04.00	3469.00										NE QUAD OF 028-0004	
81+35.00 TO 116+04.00		3469.00						44			NE QUAD OF 028-0004	
116+04.00 TO 118+74.00								4	270.00		NE QUAD OF 028-0004	
123+48.00 TO 130+45.80	697.80										SE QUAD OF 028-0004	
123+48.00 TO 132+41.75		893.75						12			SE QUAD OF 028-0004	
132+41.75 TO 132+91.75			1					1		1	SE QUAD OF 028-0004	
120+67.00 TO 123+48.00								4	281.00		SE QUAD OF 028-0004	
156+80.00 TO 157+32.00	52.00										NE QUAD OF 028-0039	
156+73.58 TO 157+17.33		43.75		1				1			NE QUAD OF 028-0039	
157+17.33 TO 157+32.00					1			1			NE QUAD OF 028-0039	
<b>SUBTOTAL (FRANKLIN CO. NB)</b>	<b>10982</b>	<b>12521</b>	<b>9</b>	<b>6</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>197</b>	<b>995</b>	<b>9</b>	<b>117</b>	

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GUARDRAIL SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			57	**	.	98	33	
		CHECKED -	REVISED -			CONTRACT NO. 78175					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.			