

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1324	03-00097-01-PV	COOK	82	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		


CONTRACT # 83971

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	**CMAQ/NCPD		***TCSP	
				ROADWAY/ DRAINAGE	TRAFFIC SIGNALS	HIGHWAY LIGHTING	LANDSCAPING
				CONSTRUCTION TYPE CODE			
				1000-2A	Y031-1F	Y030-1E	Y003
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	96	96			
20101100	TREE TRUNK PROTECTION	EACH	46	46			
* 20101200	TREE ROOT PRUNING	EACH	46	46			
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	20	20			
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	26	26			
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10			
* 20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10			
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10			
* 20101700	SUPPLEMENTAL WATERING	UNIT	85	85			
20200100	EARTH EXCAVATION	CU YD	500	500			
20800150	TRENCH BACKFILL	CU YD	500	500			
* 25200110	SODDING, SALT TOLERANT	SQ YD	420	420			
28000510	INLET FILTERS	EACH	50	50			
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	1,000	1,000			
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	3,000	3,000			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,525	3,525			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,700	1,700			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	350	350			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	600	600			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,800	3,800			
42001300	PROTECTIVE COAT	SQ YD	1,850	1,850			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,600	1,600			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	86,000	86,000			
42400800	DETECTABLE WARNINGS	SQ FT	350	350			
44000100	PAVEMENT REMOVAL	SQ YD	2,850	2,850			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	40,250	40,250			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,520	1,520			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11,100	11,100			
44000600	SIDEWALK REMOVAL	SQ FT	71,350	71,350			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	4,000	4,000			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	750	750			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,500	2,500			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	750	750			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	944	944			
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	47	47			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			
60219530	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	3			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2			
60255500	MANHOLES TO BE ADJUSTED	EACH	91	91			
60260100	INLETS TO BE ADJUSTED	EACH	9	9			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	27	27			
60500205	FILLING CATCH BASINS	EACH	2	2			
60500305	FILLING INLETS	EACH	31	31			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	500	500			
60604800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (SPECIAL)	FOOT	11,100	11,100			
66900205	SPECIAL WASTE DISPOSAL	CU YD	300	300			
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			

- SPECIALTY ITEMS
- CMAQ/NCPD IS 80% FEDERAL, 20% LOCAL MATCH
- TCSP IS 100% FEDERAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION IL RTE 58 (DEMPSTER ST) IMPROVEMENTS
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: NKU  
DATE: 10-16-09 CHECKED BY: RY

 **McDonough Associates Inc.**  
Engineers / Architects