

LOCATION OF WORK				SANGAMON VALLEY TRAIL	STUART PARK CONNECTOR	CENTENNIAL PARK & STUART PARK	STRUCTURES	STRUCTURES
				STA 917+16.90 TO STA 1207+75	STA 5999+92.48 TO STA 6015+29.93	PARKING LOT, CONNECTORS, EXISTING STUART PARK PATH	SVT OVER OLD JACKSONVILLE RD, WASHINGTON ST & JEFFERSON ST,	SVT OVER SPRING CREEK & SPRING CREEK TRIBUTARY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	Y047	Y047	Y047	Y047	Y047
20100500	TREE REMOVAL ACRES	ACRE	0.2	0.1		0.1		
20200100	EARTH EXCAVATION	CU YD	16,800	16,445	40	315		
20400800	FURNISHED EXCAVATION	CU YD	2,780		2,780			
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	16,194	16,194				
25100630	EROSION CONTROL BLANKET	SQ YD	3,376	1,462	1,914			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,090	980	80	30		
28000305	TEMPORARY DITCH CHECKS	FOOT	850	800	50			
28000400	PERIMETER EROSION BARRIER	FOOT	59,541	55,337	2,660	1,544		
28000500	INLET AND PIPE PROTECTION	EACH	10	1	6	3		
* 28100208	STONE RIPRAP, CLASS A4 (SPECIAL)	TON	146	74	16	16	40	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	14,765	12,853	716	1,196		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	25					25
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,822	9,383	537	902		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	148			148		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5,921	5,256	295	370		
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	925	925				
42400800	DETECTABLE WARNINGS	SQ FT	326	326				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1					1
* 50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1				1	
50102400	CONCRETE REMOVAL	CU YD	22.3				21.0	1.3
50157300	PROTECTIVE SHIELD	SQ YD	70				70	
50200100	STRUCTURE EXCAVATION	CU YD	39				39	
50300225	CONCRETE STRUCTURES	CU YD	35.5				35.5	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20.2					20.2
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1	
50700105	TREATED TIMBER	F.B.M.	103,459				55,071	48,388
50700305	HARDWARE	POUND	15,145				10,125	5,020
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,290				3,530	2,760

\* SEE SPECIAL PROVISIONS

CUMMINS ENGINEERING CORPORATION	JOB = 2192	DESIGNED - NAK	REVISED -	SANGAMON VALLEY TRAIL	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	FILE NAME = 2192500.dgn	DRAWN - AJH	REVISED -			05-00173-00-BT	SANGAMON	173	3	
	PLOT SCALE = 100.0000' / IN.	CHECKED - NAK	REVISED -			CONTRACT NO.				
	PLOT DATE = 1/11/2010	DATE - 3/13/2009	REVISED -			FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	0-8520		