

LOCATION OF WORK				SANGAMON VALLEY TRAIL	STUART PARK CONNECTOR	CENTENNIAL PARK & STUART PARK	STRUCTURES	STRUCTURES
				STA 917+16.90 TO STA 1207+75	STA 5999+92.48 TO STA 6015+29.93	PARKING LOT, CONNECTORS, EXISTING STUART PARK PATH	SVT OVER OLD JACKSONVILLE RD, WASHINGTON ST & JEFFERSON ST,	SVT OVER SPRING CREEK & SPRING CREEK TRIBUTARY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	Y047	Y047	Y047	Y047	Y047
△ *	B2004116	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12	6		6	
△ *	C2003272	SHRUB, HAMAMELIS VERNALIS (VERNAL WITCH HAZEL), 6' HEIGHT, BALLED AND BURLAPPED	EACH	3	3			
*	X0321158	PARK BENCHES	EACH	7	3		4	
△ *	X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	1,205			1,205	
*	X0323378	CONCRETE PARKING BLOCKS	EACH	24			24	
*	X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	7,677			7,677	
△ *	B2000770	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6			
*	XX001011	BICYCLE RACKS	EACH	7	3		4	
*	XX003155	REMOVAL OF EXISTING SUBSTRUCTURE	L SUM	1			1	
*	XX006785	TIMBER BICYCLE RAILING	FOOT	3,208	2,348	860		
△ *	A2001820	TREE, ACER SACCHARUM GREEN MOUNTAIN (GREEN MOUNTAIN SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	3		1	
*	Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1			1	
*	XX008340	TIMBER BRIDGE APPROACH RAILING	FOOT	320	320			
	54208405	PIPE CULVERTS, CLASS D, TYPE 3 EQUIVALENT ROUND-SIZE 120"	FOOT	115	115			
*	XX008341	BRIDGE FENCE RAILING (SPECIAL)	SQ FT	3,132			3,132	
*	XX008342	REMOVAL OF EXISTING TIMBER MATERIALS - LOCATION 1	L SUM	1				1
*	XX008343	REMOVAL OF EXISTING TIMBER MATERIALS - LOCATION 2	L SUM	1			1	
*	XX008344	RAIL ANCHOR ASSEMBLIES	EACH	18				18
*	X0350800	BOLLARD	EACH	22	22			
*	XX007309	BOLLARDS, QUICK RELEASE	EACH	11	11			
*	XX008345	MILE MARKERS	EACH	6	6			
△ *	K1005421	SEEDING, SPECIAL	ACRE	4.4	3.3	0.8	0.3	
△ *	K1004572	PRAIRIE SEEDING, SPECIAL	ACRE	6.5	6.5			
*	XX006670	TRAIL HEAD SIGN, COMPLETE	EACH	5	3		2	

4A

• SEE SPECIAL PROVISIONS    △ SPECIALTY ITEMS

CUMMINS ENGINEERING CORPORATION

JOB = 2192	DESIGNED - NAK	REVISED -
FILE NAME = 2192500.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = 6/9/2009	DATE - 3/13/2009	REVISED -

SANGAMON VALLEY TRAIL

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00173-00-BT	SANGAMON	173	4A
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT NO.
				08529