

TREE REMOVAL ACRES	
LOCATION	ACRE
SANGAMON VALLEY TRAIL	
LT STA 1085+85 TO STA 1086+35	0.1
PARK CONNECTOR	
RT STA. 400+20 TO STA. 401+60	0.05
LT STA. 400+20 TO STA. 401+60	0.05
TOTAL	0.20

EARTHWORK

LOCATION	EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
PARKING LOT				
STA 9+13 TO STA 11+76.90	10	8	30	-22
SANGAMON VALLEY TRAIL				
STA 917+27.90 TO STA 930+00.00	1050	788	4	784
STA 930+00.00 TO STA 945+00.00	969	727	39	688
STA 945+00.00 TO STA 955+12.25	537	403	569	-166
STA 955+68.20 TO STA 956+25.80	19	14	0	14
STA 956+47.90 TO STA 959+00.00	283	212	45	167
STA 959+00.00 TO STA 974+00.00	741	556	52	504
STA 974+00.00 TO STA 981+59.70	217	163	183	-20
STA 981+83.20 TO STA 988+00.00	128	96	153	-57
STA 988+00.00 TO STA 1003+00.00	505	379	184	195
STA 1003+00.00 TO STA 1016+82.75	242	182	316	-134
STA 1016+86.65 TO STA 1017+01.70	5	4	0	4
STA 1017+41.90 TO STA 1017+56.90	5	4	0	4
STA 1017+60.90 TO STA 1018+00.00	5	4	3	1
STA 1018+00.00 TO STA 1033+00.00	161	121	245	-124
STA 1033+00.00 TO STA 1042+66.10	333	250	7	243
STA 1042+88.90 TO STA 1047+00.00	258	194	0	194
STA 1047+00.00 TO STA 1053+25.50	425	319	0	319
STA 1056+81.50 TO STA 1061+65.20	388	291	5	286
STA 1061+85.30 TO STA 1062+00.00	5	4	0	4
STA 1062+00.00 TO STA 1076+00.00	870	653	44	609
STA 1076+00.00 TO STA 1091+00.00	333	250	833	-583
STA 1091+00.00 TO STA 1106+00.00	683	512	410	102
STA 1106+00.00 TO STA 1121+00.00	1,435	1076	44	1032
STA 1121+00.00 TO STA 1122+77.83	303	227	1	226
STA 1124+78.17 TO STA 1136+00.00	748	561	156	405
STA 1136+00.00 TO STA 1151+00.00	370	278	579	-301
STA 1151+00.00 TO STA 1166+00.00	572	429	257	172
STA 1166+00.00 TO STA 1167+07.39	20	15	14	1
STA 1171+07.06 TO STA 1181+00.00	446	335	74	261
STA 1181+00.00 TO STA 1188+75.68	277	208	434	-226
STA 1189+22.01 TO STA 1196+00.00	147	110	154	-44
STA 1196+00.00 TO STA 1200+00.00	198	149	31	118
STA 1200+00.00 TO STA 1207+75.00	3,767	2825	4,526	-1701
CONNECTOR				
LT STA 1027+81	0	0	50	-50
LT STA 1089+10.5	0	0	300	-300
STUART PARK CONNECTOR				
STA 6000+25.00 TO STA 6015+29.93	40	30	5,320	-5290
PARK CONNECTOR				
STA 400+50.00 TO STA 404+00.00	60	45	283	-238
EXISTING STUART PARK PATHWAY				
STA 608+50.00 TO STA 614+02.00	245	184	40	144
TOTAL	16,800	12,610	15,390	-2780

TOPSOIL, FURNISH AND PLACE 6"

LOCATION	SQ YD
STA 917+27.90 TO STA 930+00.00	565.32
STA 930+00.00 TO STA 945+00.00	666.60
STA 945+00.00 TO STA 955+12.25	1,005.45
STA 955+68.20 TO STA 956+25.80	1,005.45
STA 956+47.90 TO STA 959+00.00	112.04
STA 959+00.00 TO STA 974+00.00	666.61
STA 974+00.00 TO STA 981+59.00	337.30
STA 981+83.20 TO STA 988+00.00	274.12
STA 988+00.00 TO STA 1003+00.00	666.61
STA 1003+00.00 TO STA 1016+83.00	1,592.41
STA 1016+86.65 TO STA 1017+01.70	6.69
STA 1017+41.90 TO STA 1017+56.90	6.67
STA 1017+60.00 TO STA 1018+00.00	17.78
STA 1018+00.00 TO STA 1033+00.00	916.62
STA 1033+00.00 TO STA 1042+66.10	429.35
STA 1042+88.90 TO STA 1047+00.00	182.70
STA 1047+00.00 TO STA 1053+24.30	277.44
STA 1056+81.75 TO STA 1061+65.20	214.85
STA 1061+85.30 TO STA 1062+00.00	6.53
STA 1062+00.00 TO STA 1076+00.00	622.17
STA 1076+00.00 TO STA 1091+00.00	1,222.19
STA 1091+00.00 TO STA 1106+00.00	861.05
STA 1106+00.00 TO STA 1121+00.00	749.94
STA 1121+00.00 TO STA 1122+73.90	188.40
STA 1124+75.50 TO STA 1136+00.00	499.73
STA 1136+00.00 TO STA 1151+00.00	666.60
STA 1151+00.00 TO STA 1166+00.00	666.60
STA 1166+00.00 TO STA 1167+54.50	68.66
STA 1171+05.75 TO STA 1181+00.00	441.84
STA 1181+00.00 TO STA 1188+78.00	776.33
STA 1189+20.00 TO STA 1196+00.00	302.20
STA 1196+00.00 TO STA 1200+00.00	177.75
TOTAL	16,194.00

STONE RIPRAP, CLASS A4 (SPECIAL)

LOCATION	TON
SVT	
LT. STA. 1206+40	37
RT. STA. 1206+10	37
SN 084-9912	40
STUART PARK CONNECTOR	
RT. STA. 6001+88	16
PARK CONNECTOR	
LT. STA. 402+63	16
TOTAL	146

CULVERT SCHEDULE

LOCATION	TYPE	PIPE	PIPE	PIPE	STEEL END SECTIONS 12"	STEEL END SECTIONS 18"
		CULVERTS TYPE III CS CP EQRS 120" FOOT	CULVERTS CLASS D TYPE I 12" FOOT	CULVERTS CLASS D TYPE I 18" FOOT		
SVT						
STA 1027+80	AR			32		
STA 1206+25	AR	115				
STUART PARK CONNECTOR						
STA 6001+88	AR			50		2
STA 6009+93	AR		5 @ 19'		10	
PARK CONNECTOR						
STA 400+15	AR		2 @ 23'		4	
STA 402+63	AR			45		2
TOTAL		115	141	127	14	4

CUMMINS
ENGINEERING
CORPORATION

JOB = 2192	DESIGNED - NAK	REVISED -
FILE NAME = 2192schedule.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 1/8" = 100.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = 6/8/2009	DATE - 3/11/2009	REVISED -

SANGAMON VALLEY TRAIL

SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00173-00-BT	SANGAMON	173	11
CONTRACT NO.			08522	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				