

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	65
20300100	CHANNEL EXCAVATION	CU YD	811
20400800	FURNISHED EXCAVATION	CU YD	1317
25000200	SEEDING, CLASS 2	ACRE	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8
25100115	MULCH, METHOD 2	ACRE	0.4
28000400	PERIMETER EROSION BARRIER	FOOT	946
28100113	STONE RIPRAP, CLASS A7	SQ YD	1122
28200200	FILTER FABRIC	SQ YD	1322
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	570
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	72
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	121
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	90
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	832
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	152
50300225	CONCRETE STRUCTURES	CU YD	121.3
50300280	CONCRETE ENCASEMENT	CU YD	11.2
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3948
50800105	REINFORCEMENT BARS	POUND	12390
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5460
Δ 50901050	STEEL RAILING, TYPE SM	FOOT	286
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1102
51202305	DRIVING PILES	FOOT	462
51203610	TEST PILE STEEL HP12X63	EACH	2
51204650	PILE SHOES	EACH	16
51500100	NAME PLATES	EACH	1
54213450	END SECTIONS 15"	EACH	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	50
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	439
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	846
Δ 63000002	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6.75 FOOT POSTS	FOOT	350
Δ 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1
• 70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	343
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
Δ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
Δ LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	4
• X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1
• X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1
X5080600	MECHANICAL SPLICERS	EACH	56
• Z0065000	SETTING PILES IN ROCK	EACH	16

• SPECIAL PROVISIONS
Δ SPECIALTY ITEMS

LAST SAVED = 1/28/2010
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 1/28/2010 12:39:30 PM

FILE NAME =
USER NAME = bschmidt
DESIGNED -
DRAWN -
CHECKED -
DATE -

DESIGNED -
DRAWN -
CHECKED -
DATE -

DESIGNED -
DRAWN -
CHECKED -
DATE -

DESIGNED -
DRAWN -
CHECKED -
DATE -

DESIGNED -
DRAWN -
CHECKED -
DATE -



WASHINGTON COUNTY
HIGHWAY DEPARTMENT

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. 836
COUNTY HIGHWAY 8

CONTRACT NO. 97402

SECTIONS 07-00077-01-BR

TOTAL SHEETS 27
SHEET NO. 3