80% FED
20% STATE
URBAN

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0047		
~~78000200~~	~~THERMOPLASTIC PAVEMENT MARKING - LINE 4"~~	~~FOOT~~	~~4108~~	~~4108~~		
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -	FOOT	1410	1410		
	LINE 4"					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	46	46		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	46	46		
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	470	470		
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	2176	2176		
X6061702	CONCRETE MEDIAN, TYPE SM (DOWELLED)	SQ FT	2176	2176		
X7010035	TRAFFIC CONTROL AND PROTECTION, STANDARD	EACH	2	2		
	701423 (SPECIAL)					
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	363	363		
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	4108	4108		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	20	20		
Z0001905	STRUCTURAL STEEL REPAIR	POUND	1380	1380		

80% FED
20% STATE
URBAN

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0047		
Z0012110	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE	SQ YD	2733	2733		
	OVERLAY, 2 1/4"					
Z0012142	BRIDGE DECK SCARIFICATION 2 1/4"	SQ YD	2733	2733		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO	SQ FT	425	425		
	OR LESS THAN 5 INCHES)					
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	22	22		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	137	137		

* SPECIALTY ITEM

REVISED 4-13-2021

REV. - MS

USER NAME = steffenmk	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 1/22/2021	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	D7 BRIDGE REPAIRS 2021-7	MACON	33	4

CONTRACT NO. 74994

ILLINOIS | FED. AID PROJECT

MODEL: Default
FILE NAME: pw:\\dlanroom.dot.illinois.gov:IWIDOT\Documents\IDOT Offices\District 7\Projects\74994\CADData\CADsheets\D774994-sht-SQQ.dgn