

CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				1000-2A ROADWAY	Y031-1F TRAFFIC SIGNALS - CASEY RD 51 LIBERTYVILLE	Y031-1F TRAFFIC SIGNALS - ARBOR BLVD 51 WARREN TWP.	Y031-1F TRAFFIC SIGNAL INTERCONNECT	1000-2A ROADWAY
				80% FED 20% STATE	80% FED 10% STATE 5% LAKE CTY	80% FED 10% STATE 5% GRAYSLAKE	80% FED 20% STATE	100% STATE
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8		4	4		
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	120		60	60		
* 87900200	DRILL EXISTING HANDHOLE	EACH	1				1	
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		4	4		
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	4		0	4		
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	12		8	4		
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	24		12	12		
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	20		10	10		
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	68		0	68		
* 88700200	LIGHT DETECTOR **	EACH	5		2	3		
* 88700300	LIGHT DETECTOR AMPLIFIER **	EACH	2		1	1		
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	2			2		
* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY) 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3		3			
* A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5		5			
* A2002820	TREE, CATALPA SPECIOSA (NORTHERN CATALPA) 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9			
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEE TREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9			
* A2004720	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11		11			
* A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	21		21			
* A2006522	TREE, ULMUS PARVIFOLIA 'ALLEE' (ALLEE LACEBARK ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4		4			
* A2002470	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	7		7			
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8		8			
* B2006270	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	10		10			
* C2C06265	SHRUB, RHUS TYPHINA "TIGER EYES" (TIGER EYES CUTLEAF STAGHORN SUMAC), CONTAINER GROWN, 5-GALLON	EACH	15		15			
* A2018720	TREE, ULMUS CARPINIFOLIA MORTON, (ACCOLADE ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	13		13			

** PAID FOR 100% BY GRAYSLAKE FIRE PROTECTION DISTRICT - Y031-10

Rev. 4-7-09

FILE NAME =	USER NAME = #USER#	DESIGNED - MAP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JRH	REVISED -			344	(46-1S&47)WRS-3	LAKE	176	12	
	PLOT SCALE = #SCALE#	CHECKED - JW	REVISED -			U.S. ROUTE 45 RECONSTRUCTION CONTRACT NO.					
	PLOT DATE = #DATE#	DATE - 01-03-08	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					
					SCALE: NONE	SHEET NO. 9 OF 11 SHEETS		STA.	TO STA.		