

PERMANENT SURVEY MARKERS, TYPE 2

LOCATION	QUANTITY (EACH)
JOBSITE	1
TOTAL	1

ENGINEER'S FIELD OFFICE, TYPE A

LOCATION	QUANTITY (CAL MO)
JOBSITE	12
TOTAL	12

MOBILIZATION

LOCATION	QUANTITY (L SUM)
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201

LOCATION STATION	QUANTITY (L SUM)
81+97.89 TO 83+00.00	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, FOR TEMPORARY DETOUR

LOCATION STATION	QUANTITY (EACH)
83+00.00 TO 91+55.94	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE

LOCATION	QUANTITY (CAL DAY)
•JOBSITE	120
TOTAL	120

CHANGEABLE MESSAGE SIGN

LOCATION	QUANTITY (CAL MO)
JOBSITE	24
TOTAL	24

SHORT-TERM PAVEMENT MARKING

LOCATION	QUANTITY (FOOT)
JOBSITE	1200
TOTAL	1200

TEMPORARY PAINT PAVEMENT MARKING, LINE 4"

LOCATION	QUANTITY (FOOT)
JOBSITE	2000
TOTAL	2000

THERMOPLASTIC PAVEMENT MARKING LINE, 12"

LOCATION STATION	QUANTITY (FOOT)
WHITE (SOLID)	
SHOULDER GORE LINES	
81+97.89 TO 82+36.60 LT	
91+97.00 TO 92+72.60 RT	24.1
CROSS-WALK DIAGONALS	33.6
91+29.90 TO 91+75.40 RT	
SUBTOTAL	84.4
YELLOW	142.1
MEDIAN GORE LINES	
81+97.89 TO 83+62.80 MED	
TOTAL	71.9
	214.0

WORKZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ FT)
JOBSITE	1070
TOTAL	1070

THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS

LOCATION STATION	AREA PER ARROW (SQ FT)	QUANTITY (SQ FT)
ARROW		
81+97.89 TO 83+62.80 (1)	15.6	15.6
84+59.00 TO 86+64.00 (2)	15.6	31.2
88+89.00 TO 90+94.00 (2)	15.6	31.2
91+86.30 TO 92+72.60 (1)	15.6	15.6
SUBTOTAL		93.6
"ONLY"		
81+97.89 TO 83+62.80 (1)	20.8	20.8
84+59.00 TO 86+64.00 (2)	20.8	41.6
88+89.00 TO 92+72.60 (1)	20.8	41.6
91+86.30 TO 92+72.60 (1)	20.8	20.8
SUBTOTAL		124.8
TOTAL		218.4

THERMOPLASTIC PAVEMENT MARKING LINE, 4"

LOCATION STATION	QUANTITY (FOOT)
WHITE (SOLID)	
81+97.89 TO 82+38.60 LT	55.6
81+97.89 TO 83+72.10 RT	224.7
82+59.60 TO 91+34.40 LT	927.5
84+21.90 TO 91+42.00 RT	804.2
91+78.50 TO 92.72.60 RT	137.1
91+78.50 TO 92+72.60 LT	141.1
SUBTOTAL	2290.2
DOUBLE YELLOW (SOLID)	
81+97.89 TO 83+62.78 RT	333.0
81+97.89 TO 83+62.78 LT	330.1
84+59.00 TO 90+94.00 C	1270.0
91+86.30 TO 92+72.60 C	172.6
SUBTOTAL	2105.7
WHITE (TURN LANE TAPER)	
81+97.89 TO 82+59.00 RT	16.0
86+64.00 TO 88+89.00 RT	58.0
86+64.00 TO 88+89.00 LT	58.0
SUBTOTAL	132.0
YELLOW (30' SKIP, 10' DASH)	
SOUTH POINT DRIVE	30
SUBTOTAL	30
TOTAL	4557.9

THERMOPLASTIC PAVEMENT MARKING LINE, 6"

LOCATION STATION	QUANTITY (FOOT)
WHITE (SOLID)	
TURN LANE	
82+59.00 TO 83+62.50 LT	103.4
84+59.00 TO 86+64.00 RT	205.0
88+89.10 TO 90+94.00 LT	204.9
91+86.30 TO 92+72.60 RT	86.3
CROSSWALK EDGES	
91+29.90 TO 91+75.40 RT	46.3
91+33.20 TO 91+70.30 RT	36.9
TOTAL	682.8

THERMOPLASTIC PAVEMENT MARKING LINE, 24"

LOCATION STATION	QUANTITY (FOOT)
WHITE (STOP BARS)	
WEST POINT DRIVE	
84+02.10 TO 84+36.40 RT	34.3
SOUTH POINT DRIVE	
91+34.30 TO 91+55.90 LT	21.9
91+55.40 TO 91+69.60 RT	14.8
TOTAL	71.0

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION STATION	QUANTITY (EACH)
ONE-WAY AMBER MARKERS	
81+97.89 TO 83+62.80	13
84+59.00 TO 86+64.00	6
89+89.00 TO 90+94.00	5
91+86.30 TO 92+72.60	3
SUBTOTAL	27
TWO-WAY AMBER MARKERS	
81+97.89 TO 83+62.80	2
84+59.00 TO 86+64.00	32
91+86.30 TO 92+72.60	6
SUBTOTAL	40
TOTAL	67

GUARDRAIL MARKERS, TYPE A

LOCATION STATION TO STATION	QUANTITY (EACH)
84+52.21 TO 86+89.71 LT	7
85+11.46 TO 86+23.96 RT	5
TOTAL	12

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)
STATION TO STATION	
81+97.89 TO 92+72.60	76
TOTAL	76

PAVEMENT MARKING REMOVAL

LOCATION STATION	LENGTH (FOOT)	QUANTITY (SQ FT)
WHITE - (SOLID, 4")		
81+97.89 TO 82+38.60 LT	55.6	18.5
81+97.89 TO 83+72.10 RT	224.7	74.9
YELLOW - (SOLID, 4")		
81+97.89 TO 83+62.80 MED	726.6	242.2
YELLOW - (SOLID, 12")		
81+97.89 TO 83+62.80 MED	46	46.0
WHITE - (DOTTED 4")		
81+97.89 TO 82+64.70 RT	16	5.3
WHITE - (SOLID, 6")		
82+64.70 TO 83+62.50 RT	97.7	48.9
ARROW SYMBOL		
82+64.70 TO 85+29.50 RT (2)		27.1
"ONLY" TEXT		
82+64.70 TO 85+29.50 RT (2)		41.6
TOTAL		504.5

*ESTIMATED QUANTITY

FILE NAME = ...D160C07-ht-chedules.Rt.dgn	USER NAME = Plotted by Administrator	DESIGNED - OWR	REVISED - 03/05/2009	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES OAK PARK AVENUE OVER UNION DRAINAGE DITCH				F.A. RTE. 2774	SECTION 0306T	COUNTY COOK	TOTAL SHEETS 55	SHEET NO. 13
PLOT SCALE = 50.00' / IN.	CHECKED - FML	REVISOR -	DATE - 10/2008		SCALE: NONE	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60C07	