

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	102	102				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	20				
20400800	FURNISHED EXCAVATION	CU YD	80	80				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	212	212				
25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2				
25100630	EROSION CONTROL BLANKET	SO YD	212	212				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10				
40600300	AGGREGATE (PRIME COAT)	TON	49	49				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	7.5	7.5				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	64	64				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2030	2030				
42001300	PROTECTIVE COAT	SO YD	15	15				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	24163	24163				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	484	484				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	362	362				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	362	362				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	120	120				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	273	273				
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14560	14560				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	218	218				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26687	26687				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	866	866				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	119	119				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	85	85				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	218	218				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26687	26687				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	866	866				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	119	119				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	85	85				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	527	527				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	527	527				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	400	400				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	129	129				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	952	952				

2/13/2009 10:48:10 AM C:\pwworking\Illinois Dept of Transportation\Projects\68041\Drawings\68041-111RS-7.dwg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

*Specialty Items

PLOT DATE: 2/13/2009