

URBAN

SUMMARY OF QUANTITIES				URBAN	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	BRIDGE
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	85	SN 016-0322	100% FED.
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	23	SFTY-2A	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	50		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	52		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SO FT	90		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	527		
44000600	SIDEWALK REMOVAL	SO FT	90		
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	676		
50102400	CONCRETE REMOVAL	CU YD	102.7		
50104000	BRIDGE RAIL REMOVAL	FOOT	211		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	117.1		
50300260	BRIDGE DECK GROOVING	SO YD	612		
50300300	PROTECTIVE COAT	SO YD	336		
50500715	JACK AND REMOVE EXISTING BEARINGS	L SUM	1		
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16,070		
50800515	BAR SPLICERS	EACH	48		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	200		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	48		
67100100	MOBILIZATION	L SUM	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	171		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	57		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	694		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	24		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4		
78300100	PAVEMENT MARKING REMOVAL	SO FT	54		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18		
* 81100700	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., GALVANIZED STEEL	FOOT	60		
* 81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"x18"x10"	EACH	2		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		
* 89502200	MODIFY EXISTING CONTROLLER	EACH	2		
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1,200		

* SPECIALTY ITEM

URBAN

SUMMARY OF QUANTITIES				URBAN	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	BRIDGE
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SO YD	634	SN 016-0322	100% FED.
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	77	SFTY-2A	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	3		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	22		
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2,061		
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SO YD	634		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	20		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	4		
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1		
* X0326357	ROADWAY LIGHTING MODIFICATIONS	L SUM	1		
* XX003079	REMOVE JUNCTION BOX	EACH	6		
* XX007743	ROADWAY LIGHTING CONDUIT REMOVAL	FOOT	40		
* B1300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x12"x6"	EACH	4		
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3		

* SPECIALTY ITEM

• Y080

PLOT DATE = 2/12/2009
 FILE NAME = 601123002.ctb
 USER = JTP
 MODEL = Default



200 West Front Street
Wheaton, IL 60187

DESIGNED - B.B.	REVISED -
DRAWN - J.T.T.	REVISED -
CHECKED - M.K.	REVISED -
DATE - 1/30/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL-43 OVER STONY CREEK
STRUCTURE NO. 016-0322

SUMMARY OF
QUANTITIES

F.A.P. RTE. 348	SECTION 3128-Z-B-1	COUNTY COOK	TOTAL SHEETS 35	SHEET NO. 3
CONTRACT NO. 60D70				

SCALE: SHEET NO. 3 OF 35 SHEETS STA. TO STA. FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

Rev.