

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2719	2008-004 RS	COOK	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60E25

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8				
40600300	AGGREGATE (PRIME COAT)	TON	39	39				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	177	177				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1648	1648				
42001300	PROTECTIVE COAT	SO YD	100	100				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	19042	19042				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	450	450				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	800	800				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	200	200				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	100	100				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3				
60404900	FRAMES AND GRATES, TYPE 12	EACH	23	23				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2740	2740				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	293	293				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10044	10044				

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	460	460				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	45	45				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	132	132				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	915	915				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	293	293				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10044	10044				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	460	460				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	45	45				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132	132				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	405	405				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	405	405				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	132	132				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	824	824				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	32	32				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

NP: Non-participating
* - Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
EAST AVENUE
55TH STREET TO 47TH STREET

PLOT DATE: 2/6/2009

2/6/2009 9:52 AM C:\WORK\PROJECTS\2008\20080206\60E25\SUMMARY\SUMMARY.DWG