

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		SFTY-2A	
			TOTAL QUANTITIES	WEST BRANCH	EAST BRANCH
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	0.5	0.5
40600300	AGGREGATE (PRIME COAT)	TON	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	620	310	310
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	116	60	56
42001300	PROTECTIVE COAT	SQ YD	1,269	708	561
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	44	22	22
50102400	CONCRETE REMOVAL	CU YD	39.5	16.4	23.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	43.1	17.6	25.5
50300260	BRIDGE DECK GROOVING	SQ YD	1,190	666	524
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,660	2,490	4,170
50800515	BAR SPLICERS	EACH	54	22	32
52000110	PREFORMED JOINT STRIP SEAL	FOOT	208	118	90
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	15	15
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6	6
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	699	312	387
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	632	360	272
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	2	4
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	2	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	4	8

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		SFTY-2A	
			TOTAL QUANTITIES	WEST BRANCH	EAST BRANCH
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0.5	0.5
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	40	40	
* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	275	275	
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	2,025	905	1,120
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	195	195	
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	11	5	6
* 83057250	LIGHT POLE, WOOD, 45 FOOT, CLASS 4	EACH	2	1	1
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT MAST ARM	EACH	11	5	6
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	11	5	6
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1,187	672	515
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	104	52	52
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4	2	2
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	3,147	1,585	1,562
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	48	24	24
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	2	1	1
* X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	4	2	2
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	10	7	3
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	8	2	6
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1,187	672	515

\* SPECIALTY ITEM

FILE NAME = D168E63-sh1-S00.dgn  
PLOT DATE = 1/29/2009



**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - JANUARY 28, 2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
U.S. 30**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. VARIOUS TO STA. VARIOUS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	117 R-2B-R	KANE	40	3
CONTRACT NO. 60E63			Rev.	