

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2008-056 I	COOK	32	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60F11

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		OUTSIDE/ INSIDE SHOULDERS	URBAN SFTY-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
<i>70300520</i>	<i>PAVEMENT MARKING TAPE, TYPE III 4"</i>	FOOT	84014	84014					
<i>70300550</i>	<i>PAVEMENT MARKING TAPE, TYPE III 8"</i>	FOOT	14083	14083					
<i>70300560</i>	<i>PAVEMENT MARKING TAPE, TYPE III 12"</i>	FOOT	5771	5771					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	43165	43165					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	84014	84014					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	14083	14083					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	5771	5771					
78300100	PAVEMENT MARKING REMOVAL	SO FT	43165	43165					
<i>X0326218</i>	<i>FIBER-MODIFIED ASPHALT CRACK SEALING</i>	<i>FOOT</i>	<i>6031</i>	<i>6031</i>					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
<del>X7013820</del>	<del>TRAFFIC CONTROL SURVEILLANCE; EXPRESSWAYS</del>	<del>CAL DA</del>	<del>11</del>	<del>11</del>					
XZ186500	ASPHALTIC EMULSION SLURRY SEAL	SO YD	94291	94291					
<i>X0326219</i>	<i>BUMP REMOVAL</i>	<i>EACH</i>	<i>280</i>	<i>280</i>					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI 290/I-290 (EISENHOWER EXPY.-WESTBOUND)  
 25TH AVENUE TO I-90/94  
 SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 12/23/2008