

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	50	50					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	50	50					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26					
40600300	AGGREGATE (PRIME COAT)	TON	129	129					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	100	100					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	295	295					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1000	1000					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6	6					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6313	6313					
42001300	PROTECTIVE COAT	SO YD	100	100					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	50	50					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	50	50					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	8500	8500					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	55888	55888					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	200	200					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1000	1000					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	5920	5920					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1288	1288					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	2700	2700					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1932	1932					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6					
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	6	6					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	25	25					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8					

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1000	1000					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5400	5400					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1200	1200					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21000	21000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3900	3900					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	650	650					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1350	1350					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	500	500					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4050	4050					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1200	1200					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21000	21000					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3600	3600					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	650	650					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1350	1350					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	500	500					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	562	562					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	390	390					

*Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 72

2/6/2009 10:00:00 AM C:\WORK\2009\10088888\10088888-10088888.dwg