



NOTES:

1. EXISTING HIGH MAST LIGHTING ON LIGHTING CONTROLLER "D1", (5) 400W FIXTURES PER TOWER IS SHOWN FOR INFORMATION ONLY- NOT PART OF THIS CONTRACT.
2. PROVIDE (2) NEW 2-POLE, 200 AMPERE, MAIN CIRCUIT BREAKERS TO REPLACE EXISTING MAIN CIRCUIT BREAKERS IN CONTROLLER "D1". INCREASE EXISTING BUS CABLE SIZE TO 4/0 AWG. ADD (4) 70 AMPERE, 2-POLE, BRANCH CIRCUIT BREAKERS.



FILE NAME =	USER NAME = default	DESIGNED - HS	REVISED -
P:_2009\C9X93680\CADD\Sheets\Lighting\Proposed_Sheet_11.dgn	Proposed_Sheet_11.dgn	DRAWN - MJO/HS	REVISED -
PLOT SCALE = #SCALE#		CHECKED - CDS	REVISED -
PLOT DATE = 3/5/2009		DATE - 3/5/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PROPOSED LIGHTING PLAN

SCALE: 1"=50' SHEET NO. OF SHEETS STA. 2700+00 TO STA.

JACOBS		ONE NORTH FRANKLIN CHICAGO IL, 60606 312-251-3000		
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	2008-081 L	COOK	18	13
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 60F83		