

SUMMARY OF QUANTITIES			URBAN 1001.FED. TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36					
40600300	AGGREGATE (PRIME COAT)	TON	176	176					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	264	264					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3570	3570					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9829	9829					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	87,755	87,755					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27273	27273					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	9091	9091					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	150000	150000					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1800	1800					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	100					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1500	1500					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1500	1500					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1000	1000					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	617	617					
0 20076600	TRAINEE	HRS	500	500					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. 4-9-09

PLOT DATE: 2/6/2009